STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (mm)	SIGN DIMENSIONS HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) 44 kg/m 3.4	SQUARE STEEL (mm) 50 kg/m 3.9	SQUARE STEEL (mm) 63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	TUBULAR ALUMINUM Ø (mm) 100 kg/m 2.5	TUBULAR ALUMINUM Ø (mm) 100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	TUBULAR STEEL Ø (mm) 89 kg/m 13.4	TUBULAR STEEL Ø (mm) 100 kg/m 16.1	TUBULAR STEEL Ø (mm) 125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
											OPTION ITEMS																										
MENDON: 2+253.1, RT	0040 1110 0140	1	150	200	0.03						1	X																							E-138M
2+254.0, LT	SCHOOL BUS STOP AHEAD	1	750	750	0.56						2			X																				E-153M
	HIDDEN DRIVE LEFT	1	750	750	0.56																													E-154M
2+558.0, LT	MEDWAY RD						1				1		X																					SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
2+558.0, LT	STOP 0040 1110 0159	1 1	750 150	750 200	0.56 0.03						1			X																				BACK-TO-BACK		E-143M E-138M
2+566.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X																					E-141M
2+568.0, LT	NO OUTLET	1	750	750	0.56						1			X																				79	-
2+595.6, RT	TRUCK LANE 500 FEET	1	600	750	0.45						1			X																					E-141M
2+703.0, RT	BRIDGE 23A US 4	1	150	200	0.03						1	X																							E-134M
2+710.0, LT	BRIDGE 23A US 4	1	150	200	0.03						1	X																							E-134M
											m	m	m	m	m	m	EA		kg	kg	kg		kg	kg	kg	kg							
											13.8	4.6	27.6																						
TOTALS			m^2 3.26	m^2	EA 1	m^2					m 46.0			m					kg	EA	kg						EA	EA	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

ARCHIVED IN DPR

PROJECT:	PROJECT NO.:
RUTLAND - KILLINGTON	NH 9809(I)S

DESIGN FILE NAME: /pave/97bl60/pbl60.dgn
IPARM FILE NAME: pbl60t10.i
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
PLOT DATE: 11/99
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 55 OF 83