STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44, kg/m 3.4	50, 3.9	63, 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75, kg/m 1.9	100, 2.5	100 MOD, 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) 75, kg/m 11.3	89, 13.4	100, 16.1	125, 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
															OPTION ITEMS																				
KILLINGTON: 0+000.0, LT	MENDON | KILLINGTON	1	1500	190	0.29						1		X																						E-124M
	0040 1121 0000	1	150	200	0.03																														E-138M
0+148.0, LT	OLD COACH RD						1				1		X																				SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
0+148.0, LT	STOP 0040 1121 0010	1 1	750 150	750 200	0.56 0.03						1			X																			BACK-TO-BACK		E-143M E-138M
0+160.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X																					E-141M
0+170.0, RT		1	600	600	0.36						1			X																					E-143M
	BEGIN	1	600	300	0.18																														E-140M
0+206.0, RT		1	600	600	0.36						1			X																					E-143M
0+295.0, RT		1	600	600	0.36						1			X																					E-143M
0+319.0, RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X																					E-141M
												m	m 9.2	m 27.6	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS					m² 3.07	m²	EA 1	m²				m 36.8			m					kg			EA	kg				EA	EA	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

ARCHIVED IN DPR

PROJECT: RUTLAND - KILLINGTON
PROJECT NO.: NH 9809(1)S

DESIGN FILE NAME: /pave/97b160/pb160.dgn
IPARM FILE NAME: pb160t21.i
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
PLOT DATE: 11/99
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 66 OF 83