STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (mm)	SIGN DIMENSIONS HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) kg/m 44 3.4	SQUARE STEEL (mm) kg/m 50 3.9	SQUARE STEEL (mm) kg/m 63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	TUBULAR ALUMINUM Ø (mm) kg/m 100 2.5	TUBULAR ALUMINUM Ø (mm) kg/m 100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	TUBULAR STEEL Ø (mm) kg/m 89 13.4	TUBULAR STEEL Ø (mm) kg/m 100 16.1	TUBULAR STEEL Ø (mm) kg/m 125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
											OPTION ITEMS																										
KILLINGTON: 1+228.0, LT							1				1			X																				SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
	LONG TRAIL						1																											SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
	APPALACHIAN TRAIL						1																											SALVAGED SIGN TO BE MOUNTED ON NEW POST.	-	-
1+287.5, RT	0040 1121 0080	1	150	200	0.03						1	X																								E-138M
1+303.3, RT	SPEED LIMIT 50	1	600	750	0.45						1			X																						E-142M
1+314.0, LT		1	750	750	0.56						1			X																						E-152M
1+374.0, LT	WATCH FOR TURNING VEHICLES	1	900	900	0.81						2			X																						E-154M
1+398.0, RT	UNSAFE TO PASS	1	900	900	0.81						2			X																						E-150M
1+428.0, RT		1	900	900	0.81						2			X																						E-151M
1+609.3, LT	0040 1121 0100	1	150	200	0.03						1	X																								E-138M
1+617.0, RT	LEFT TURN OR U-TURN AHEAD	1	1600	1500		2.40					2										X														79	-
1+815.6, LT	SPEED LIMIT 50	1	600	750	0.45						1			X																						E-142M
1+840.0, RT		1	450	450	0.20						1	X																								E-150M
												m 13.8	m	m 46.0	m	m	m		EA	kg	kg 29.0	kg		kg	kg	kg	kg								
	TOTALS				m^2 4.15	m^2 2.4	EA 3	m^2				m 59.8			m					kg 29.0			EA	kg				EA	EA	kg						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

ARCHIVED IN DPR

PROJECT:	PROJECT NO.:
RUTLAND - KILLINGTON	NH 9809(I)S

DESIGN FILE NAME: /pave/97bl60/pbl60.dgn
IPARM FILE NAME: pbl60t25.i
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
PLOT DATE: 11/99
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 70 OF 83