STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (mm)	SIGN DIMENSIONS HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) 44 kg/m 3.4	SQUARE STEEL (mm) 50 kg/m 3.9	SQUARE STEEL (mm) 63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	TUBULAR ALUMINUM Ø (mm) 100 kg/m 2.5	TUBULAR ALUMINUM Ø (mm) 100 MOD kg/m 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	TUBULAR STEEL Ø (mm) 89 kg/m 13.4	TUBULAR STEEL Ø (mm) 100 kg/m 16.1	TUBULAR STEEL Ø (mm) 125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																									
	SHEET SUBTOTALS																																			
	SHEET 46 SUBTOTALS				7.78	-	-					-	-	41.4							-															
	SHEET 47 SUBTOTALS				5.72	-	3					4.6	-	27.6							-															
	SHEET 48 SUBTOTALS				4.63	-	1					4.6	-	41.4							-															
	SHEET 49 SUBTOTALS				4.35	-	8					-	9.2	36.8							-															
	SHEET 50 SUBTOTALS				3.94	-	1					9.2	4.6	41.4							-															
	SHEET 51 SUBTOTALS				3.82	-	-					9.2	-	36.8							-															
	SHEET 52 SUBTOTALS				3.86	-	-					4.6	4.6	36.8							-															
	SHEET 53 SUBTOTALS				4.03	-	3					-	-	46.0							-															
	SHEET 54 SUBTOTALS				3.52	-	1					-	4.6	32.2							-															
	SHEET 55 SUBTOTALS				3.26	-	1					13.8	4.6	27.6							-															
	SHEET 56 SUBTOTALS				4.15	-	-					9.2	-	41.4							-															
	SHEET 57 SUBTOTALS				2.87	-	2					13.8	-	36.8							-															
	SHEET 58 SUBTOTALS				2.87	-	3					9.2	4.6	32.2							-															
	SHEET 59 SUBTOTALS				3.34	-	1					4.6	4.6	32.2							-															
	SHEET 60 SUBTOTALS				3.79	-	2					4.6	9.2	36.8							-															
	SHEET 61 SUBTOTALS				2.95	-	2					9.2	4.6	32.2							-															
	SHEET 62 SUBTOTALS				3.46	-	-					9.2	-	32.2							-															
	SHEET 63 SUBTOTALS				3.87	-	-					13.8	-	41.4							-															
	SHEET 64 SUBTOTALS				3.32	-	-					18.4	-	32.2							-															
	SHEET 65 SUBTOTALS				4.46	-	-					18.4	-	46.0							-															
	SHEET 66 SUBTOTALS				3.07	-	1					-	9.2	27.6							-															
	SHEET 67 SUBTOTALS				3.54	-	2					-	9.2	32.2							-															
	SHEET 68 SUBTOTALS				4.15	-	1					4.6	4.6	41.4							-															
	SHEET 69 SUBTOTALS				5.16	-	3					4.6	-	55.2							-															
	SHEET 70 SUBTOTALS				4.15	2.4	3					13.8	-	46.0							29.0															
	SHEET 71 SUBTOTALS				5.25	-	1					-	4.6	41.4							-															
	SHEET 72 SUBTOTALS				5.39	-	-					9.2	-	46.0							-															
	SHEET 73 SUBTOTALS				5.02	-	-					13.8	-	41.4							-															
	SHEET 74 SUBTOTALS				3.28	-	4					9.2	-	32.2							-															
	SHEET 75 SUBTOTALS				6.31	-	-					4.6	-	59.8							-															
	SHEET 76 SUBTOTALS				5.28	-	1					-	4.6	41.4							-															
	SHEET 77 SUBTOTALS				5.45	-	-					-	-	55.2							-															
	ROUNDING				1.96	0.6	-					13.8	7.2	28.8							1.0															
												m 230	m 90	m 1280	m	m	m	EA -	EA -	kg -	kg 30	kg -		kg	kg	kg	kg								
	TOTALS				m^2 138	m^2 3	EA 44	m^2				m 1600			m					kg 30			EA	kg				EA	EA	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

ARCHIVED IN DPR

PROJECT:	PROJECT NO.:
RUTLAND - KILLINGTON	NH 9809(I)S

DESIGN FILE NAME: /pave/97bl60/pbl60.dgn
IPARM FILE NAME: pbl60t33.i
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.

PLOT DATE: 11/99
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 78 OF 83