QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			FULL C.E.	EMPLOYEE TRAINEESHIP	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
			-	-	-	10	10	CY	COMMON EXCAVATION	203.15	EST.
			-	-	-	580	580	CY	EARTH BORROW	203.30	22
			-	-	-	16,000	16,000	SY	COLD PLANING - BITUMINOUS PAVEMENT	210.10	321
			-	-	-	200	200	TON	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.28	EST.
			-	-	-	10	10	TON	AGGREGATE SHOULDERS	402.12	EST.
			-	-	-	1900	1900	TON	AGGREGATE SHOULDERS (MOD.)	402.12	83
			-	-	-	625	625	CWT	EMULSIFIED ASPHALT	404.65	24
			-	-	-	1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	-
			-	-	-	25,900	25,900	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 64-28)	490.30	1214
			-	-	150	-	150	LF	BRIDGE EXPANSION JOINT (ASPHALTIC PLUG)	516.10	6
			-	-	-	3	3	EA	CHANGING ELEVATIONS OF DI's, CB's OR MH's	604.40	-
			-	-	-	1	1	EA	REHABING DI's, CB's OR MH's, CLASS I	604.412	-
			-	-	-	90	90	HR	POWER GRADER RENTAL	608.15	EST.
			-	-	-	75	75	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
			-	-	-	100	100	HR	POWER BROOM RENTAL	608.30	EST.
			-	-	-	10	10	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
			-	-	-	150	150	HR	TRUCK RENTAL	608.37	EST.
			-	-	-	90	90	CY	STONE FILL, TYPE I	613.10	3
			-	-	-	105	105	EA	YIELDING MARKER POSTS	619.17	-
			-	-	-	5400	5400	LF	STEEL BEAM GUARDRAIL (GALVANIZED)	621.20	183
			-	-	-	100	100	LF	STEEL BEAM GUARDRAIL (GALVANIZED) (MOD. - 8' POSTS)	621.20	-
			-	-	-	28	28	EA	MANUFACTURED TERMINAL SECTION (FLARED)	621.505	-
			-	-	-	1	1	EA	MANUFACTURED TERMINAL SECTION (TANGENT)	621.505	-
			-	-	-	2	2	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	-
			-	-	-	2	2	EA	GUARDRAIL APPROACH SECTION, TYPE I (GALVANIZED)	621.70	-
			-	-	-	2	2	EA	GUARDRAIL APPROACH SECTION, TYPE II (GALVANIZED)	621.71	-
			-	-	-	6100	6100	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	210
			-	-	-	1600	1600	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
			-	-	-	2400	2400	HR	FLAGGERS	630.15	EST.
			1	-	-	-	1	LS	FIELD OFFICE - ENGINEERS	631.10	-
			1	-	-	-	1	LS	TESTING EQUIPMENT - CONCRETE	631.16	-
			1	-	-	-	1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	-
			1	-	-	-	1	LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25	-
			-	520	-	-	520	HR	EMPLOYEE TRAINEESHIP	634.10	EST.
			-	-	-	1	1	LS	MOBILIZATION / DEMOBILIZATION	635.11	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING-BITUMINOUS PAVEMENT
12908	SY	MAINLINE
1846	SY	SIDE ROADS
925	SY	DRIVEWAYS
321	SY	ROUNDING
16,000	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 64-28)
2641	TON	LEVELING COURSE (TYPE IVS)
21,505	TON	WEARING COURSE (TYPE IIIS)
223	TON	SIDE ROADS
317	TON	DRIVEWAYS AND PARKING AREAS
1214	TON	ROUNDING
25,900	TON	TOTAL
		AGGREGATE SHOULDERS (MOD.)
140	TON	GUARDRAIL END SECTIONS
1677	TON	SHOULDER BACK UP
83	TON	ROUNDING
1900	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

QUANTITY SHEET #1

PROJECT NAME: MIDDLEBURY - NEW HAVEN
PROJECT NUMBER: NH 9813(I)S

FILE NAME: p97bl66.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: J.S.P.
IPARM FILE: pbl66qsl.I

PLOT DATE: $DATE$
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 6 OF 63