STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																		REMARKS	SIGN DETAIL	
		EA	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft			SQUARE STEEL (in) lb/ft			ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft			FOUNDATION	TUBULAR STEEL Ø (in) lb/ft				W-SHAPE STEEL FTG. SIZE		WEIGHT	POST SIZE	SIGN FRAME REQUIRED		DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
															1.75	2.0	2.5			3.0	4.0	4.0 MOD		3.0	3.5	4.0	5.0	24"	30"						
												1.12	2.0	3.0	1.88	2.16	3.35			1.3	1.7	1.7		7.6	9.0	10.8	14.6								
		OPTION ITEMS																																	
MIDDLEBURY: 324+50.0, LT	Sheldon Museum park st. at main 1							8			2			X		X		X															MOUNT SALVAGED SIGN ON NEW POSTS.	-	-
	Fire & Ice Rest. rt. at light, left on seymour							8																									MOUNT SALVAGED SIGN ON NEW POSTS.	-	-
	Tully & Marie's bakery lane 1							8																									MOUNT SALVAGED SIGN ON NEW POSTS.	-	-
327+36.0, RT	0070 0111 0620	1	6	10	0.42						1	X			X			X															SIGN ID CODE VD-700		E-138
327+76.0, LT	40	1	36	36	9.00						2			X																			SIGN SHALL BE MOUNTED ON TWO FLANGED CHANNEL POSTS. SIGN ID CODE W3-5	58	
337+92.0, LT	0070 0111 0640	1	6	10	0.42						1	X			X			X															SIGN ID CODE VD-700		E-138
348+48.0, RT	0070 0111 0660	1	6	10	0.42						1	X			X			X															SIGN ID CODE VD-700		E-138
351+25.0, LT	EXCHANGE ST						1				1			X		X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP 0070 0111 0666	1 1	30 6	30 10	6.25 0.42																											BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
351+51.0, RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			X		X		X															SIGN ID CODE VR-017		E-141
351+99.0, LT	STOP LEGAL LOAD LIMIT 24,000 POUNDS	1 1	30 24	30 30	6.25 5.00						1			X		X		X															BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VR-017		E-143 E-141
												LF 42	LF	LF 70 (28)	LF 42	LF 70	LF		EA	LB	LB	LB		LB	LB	LB	LB							
TOTALS		SF 33.18	SF	EA. 1	SF 24							LF 112 (28)			LF 112					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: MIDDLEBURY - NEW HAVEN
PROJECT NUMBER: NH 9813(I)S

FILE NAME: p97bl66.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: J.S.P.
IPARM FILE: pbl66tss02.i
PLOT DATE: $DATE$
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 38 OF 63