



### CONSTRUCTION APPROACH SIGNING

HIGHWAY NAME	RWA	ERW	RW500	RWN	OTHER
U.S. ROUTE 7-BEGIN PROJECT	2	1	2	1	1-PORT. MESSAGE SIGN
EXCHANGE STREET (TH-73)	1	1			
HAPPY VALLEY ROAD (TH-9)	1	1			
BELDEN FALLS ROAD (TH-32)	1	1			
RIVER ROAD (TH-2)	1	1			
DOG TEAM ROAD (TH-5)	1	1			
DOG TEAM ROAD (TH-5)	1	1			
CAMPGROUND ROAD (TH-26)	1	1			
HUNT ROAD (TH-27)	1	1			
TOWN HILL ROAD (TH-3)	1	1			
VT. ROUTE 17	2	1	2		1-PORT. MESSAGE SIGN
VT. ROUTE 17	2	1	2		1-PORT. MESSAGE SIGN
U.S. ROUTE 7-END PROJECT	2	1	2	1	1-PORT. MESSAGE SIGN
TOTAL	17	13	8	2	4-PORT. MESSAGE SIGNS

#### NOTES:

- SEE VAOT STD. E-100 FOR ADDITIONAL SIGN PLACEMENT.
- CONSTRUCTION ZONE SIGN LAYOUT SHALL BE IN ACCORDANCE WITH SECTION 6 OF THE LATEST EDITION OF THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MUTCD).
- CONSTRUCTION SIGNS SHALL BE IN NEW OR LIKE NEW CONDITION PER VAOT STANDARDS.
- DIAMOND SHAPED SIGNS SHALL BE 4' X 4' WITH BLACK LEGEND ON FLUORESCENT ORANGE BACKGROUND.
- REFLECTIVE SHEETING SHALL BE TYPE VII OR BETTER.
- CONSTRUCTION ZONE SIGNS SHALL BE INSTALLED ON TWO POSTS EACH OR AS AN NCHRP 350 COMPLIANT SIGN/STAND SYSTEM.
- PORTABLE CHANGEABLE MESSAGE SIGNS SHALL BE PLACED AS DIRECTED BY THE RESIDENT ENGINEER.
- PORTABLE CHANGEABLE MESSAGE SIGNS SHALL BE PAID FOR UNDER ITEM 641.15. ALL OTHER CONSTRUCTION SIGNING SHALL BE PAID FOR UNDER ITEM 641.10.

### CONSTRUCTION APPROACH SIGNING DETAIL SHEET

PROJECT NAME: MIDDLEBURY - NEW HAVEN  
PROJECT NUMBER: NH 9813(1)S

FILE NAME: p97bi66.dgn  
PROJECT LEADER: D.E.G.  
DESIGNED BY: J.S.P.  
IPARM FILE: pbi66cas.i

PLOT DATE: \$DATE\$  
DRAWN BY: C.A.K.  
CHECKED BY: D.W.E.