STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) kg/m 44 3.4	SQUARE STEEL (mm) kg/m 50 3.9	SQUARE STEEL (mm) kg/m 63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	TUBULAR ALUMINUM Ø (mm) kg/m 100 2.5	TUBULAR ALUMINUM Ø (mm) kg/m 100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	TUBULAR STEEL Ø (mm) kg/m 89 13.4	TUBULAR STEEL Ø (mm) kg/m 100 16.1	TUBULAR STEEL Ø (mm) kg/m 125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
														OPTION ITEMS	LENGTH																						
WOODBURY 4+155 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X	4.43		*																	REFER TO STANDARD E-12IM FOR PLACEMENT.		E-14IM
4+160 RT	STOP 0140 1219 0256	1	600	600	0.36		1				1			X	3.83		*																	BACK TO BACK		E-143M
4+877 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X	3.02		*																	REFER TO STANDARD E-12IM FOR PLACEMENT.		E-14IM
4+887 RT	STOP 0140 1219 0303	1	600	600	0.36		1				1			X	3.95		*																	BACK TO BACK		E-143M
5+470 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X	4.20		*																	REFER TO STANDARD E-12IM FOR PLACEMENT.		E-14IM
5+476 RT	STOP	1	600	600	0.36						1			X	2.82		*																			E-143M
5+710 RT	WOODBURY ELEMENTARY SCHOOL LEFT	1					1																												
5+815 RT		1	750	750	0.56						1			X	4.00		*		X																	E-153M
5+932 RT		1	750	750	0.56						1			X	4.62		*		X																	E-153M
	TO	1	600	750	0.45																															E-146M
5+932 LT		1	750	750	0.56						1			X	4.62		*																			E-153M
	TO	1	600	750	0.45																															E-146M
					m² 5.01	m²	EA. 3 ~~2~~	m²			m	m	m 35.49 ~~41.4~~	m	m 35.49	m ~~41.4~~		EA. 2	kg	kg	kg	EA.	kg	kg	kg	kg	EA.	EA.	kg						
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."																																			
	SHEET TOTALS				5.01		3 ~~2~~						35.49 ~~41.4~~			~~41.4~~		2																		

ARCHIVED IN DPR

PROJECT: **WOODBURY – HARDWICK**
PROJECT NO.: **STP 9817(1)S**
DATE: 10-98

DESIGN FILE NAME: /pave/97bl74/pbl74.dgn
IPARM FILE NAME: pbl74sl.i
SURVEYED BY:
SQUAD LEADER:

PLOT DATE: 21-MAR-2008 16:5
SURVEY DATE:
DRAWN BY: C.E.A., INC.
SHEET: **20** OF **25**