

**STATE OF VERMONT
AGENCY OF TRANSPORTATION**

COMPOSITE QUANTITY SHEET 4

SUMMARY OF ESTIMATED QUANTITIES STP 0284(17)						SUMMARY OF ESTIMATED QUANTITIES CMG PARK(31)						TOTALS		DESCRIPTORS				DETAILED SUMMARY OF QUANTITIES		
	ROADWAY	TRAINING		EROSION CONTROL	FULL C.E. ITEMS	ROADWAY	TRAINING	LANDSCAPING		FULL C.E. ITEMS	EROSION CONTROL	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
	1											1		EACH	TRAFFIC CONTROL SIGNAL SYSTEM, INTERSECTION (US ROUTE 2 @ VT ROUTE 117)	678.15	-			
	70					250						320		LF	WIRED CONDUIT (1") (PVC)	678.23	-			
	140											140		LF	WIRED CONDUIT (2 1/2") (PVC)	678.23	-			
	1300					2750						4050		LF	WIRED CONDUIT (2") (PVC)	678.23	-			
	75											75		LF	WIRED CONDUIT (3") (PVC)	678.23	-			
	7											7		EACH	PULL BOX, STANDARD	678.25	-			
	11					26						37		EACH	JUNCTION BOX	678.26	-			
						2						2		EACH	PULL BOX, DOUBLE	678.27	-			
	150					275						425		LF	ELECTRICAL CONDUIT SLEEVE (6") (PVC)	678.30	31			
	475											475		LF	ELECTRICAL CONDUIT SLEEVE (8") (PVC)	678.30	9			
	1											1		EACH	REMOVAL OF EXISTING TRAFFIC CONTROL SIGNAL SYSTEM (US ROUTE 2 @ VT ROUTE 117)	678.45	-			
	8					26						34		EACH	LIGHT POLE BASE	679.21	-			
	8					26						34		EACH	LIGHT POLE	679.45	-			
						1						1		EACH	POWER DROP STANCHION, STREET LIGHTING	679.55	-			
	1					1						2		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-			
						10						10		CY	SPECIAL PROVISION (PERMANENT STONE CHECK DAM)	900.608	2			
						4						4		EACH	SPECIAL PROVISION (BICYCLE RACK)	900.620	-			
	8											8		EACH	SPECIAL PROVISION (LUMINAIRE, LED) (STP 0284 (17))	900.620	-			
						26						26		EACH	SPECIAL PROVISION (LUMINAIRE, LED) (CMG PARK (31))	900.620	-			
						1						1		EACH	SPECIAL PROVISION (REMOVAL AND DISPOSAL OF EXISTING PAYPHONE)	900.620	-			
						1						1		EACH	SPECIAL PROVISION (REMOVAL AND REPLACEMENT OF EXISTING FLUSHING BASIN IN PAVEMENT)	900.620	-			
						1						1		EACH	SPECIAL PROVISION (REMOVAL OF EXISTING AREA LIGHTING SYSTEM)	900.620	-			
	5					1						6		EACH	SPECIAL PROVISION (SOIL BEARING SLIP BASE) (2 1/2")	900.620	-			
						700						700		LF	SPECIAL PROVISION (6 INCH UNDERDRAIN PIPE, DRY SWALE)	900.640	10			
						60						60		LF	SPECIAL PROVISION (6 INCH UNDERDRAIN PIPE, DRY SWALE WITH STONE FILL)	900.640	1			
						1						1		LS	SPECIAL PROVISION (BUS SHELTER)	900.645	-			
						275						275		SY	SPECIAL PROVISION (STAMPED COLORED CONCRETE MEDIAN ISLAND, 5 INCH)	900.675	24			
						150						150		SY	SPECIAL PROVISION (STAMPED COLORED CONCRETE TRAFFIC CIRCLE, 8 INCH)	900.675	10			
						75						75		SY	SPECIAL PROVISION (UNIT BLOCK RETAINING WALL)	900.675	5			

PROJECT NAME: RICHMOND	
PROJECT NUMBER: STP 0284 (17) / CMG PARK (31)	
FILE NAME: z97c186q+ty.dgn	PLOT DATE: 4/29/2013
PROJECT LEADER: ERIK ATKINS	DRAWN BY: A. ACHARYA
DESIGNED BY: A. ACHARYA	CHECKED BY: T. BIGELOW
QUANTITY SHEET #4	SHEET 7 OF 133