STATE OF VERMONT
AGENCY OF TRANSPORTATION

# QUANTITY SHEET 3

| SUMMARY OF ESTIMATED QUANTITIES | | | | | | | | | TOTALS | | DESCRIPTIONS | | | | DETAILED SUMMARY OF QUANTITIES | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | ROADWAY | TRAINING | LANDSCAPING | EROSION CONTROL | FULL C.E. ITEMS | GRAND TOTAL | FINAL | UNIT | ITEMS | ITEM NUMBER | ROUND | QUANTITIES | UNIT | ITEMS |
| | | | | | | | 25 | | | 25 | | MGAL | LANDSCAPE WATERING | 656.65 | 1 | | | |
| | | | | | | | 35 | | | 35 | | CY | LANDSCAPE BACKFILL, TRUCK MEASUREMENT | 656.80 | 4 | | | |
| | | | | | | | 1 | | | 1 | | LS | TREE PROTECTION | 656.85 | - | | | |
| | | | | | 48 | | | | | 48 | | SF | TRAFFIC SIGNS, TYPE A | 675.20 | - | | | |
| | | | | | 284 | | | | | 284 | | LF | SQUARE TUBE SIGN POST AND ANCHOR | 675.341 | - | | | |
| | | | | | 16 | | | | | 16 | | EACH | REMOVING SIGNS | 675.50 | - | | | |
| | | | | | 13 | | | | | 13 | | EACH | ERECTING SALVAGED SIGNS | 675.60 | - | | | |
| | | | | | 5 | | | | | 5 | | EACH | DELINEATOR WITH STEEL POST | 676.10 | 3 | | | |
| | | | | | 250 | | | | | 250 | | LF | WIRED CONDUIT (1") (PVC) | 678.23 | - | | | |
| | | | | | 2750 | | | | | 2750 | | LF | WIRED CONDUIT (2") (PVC) | 678.23 | - | | | |
| | | | | | 26 | | | | | 26 | | EACH | JUNCTION BOX | 678.26 | - | | | |
| | | | | | 2 | | | | | 2 | | EACH | PULL BOX, DOUBLE | 678.27 | - | | | |
| | | | | | 275 | | | | | 275 | | LF | ELECTRICAL CONDUIT SLEEVE (6") (PVC) | 678.30 | - | | | |
| | | | | | 26 | | | | | 26 | | EACH | LIGHT POLE BASE | 679.21 | - | | | |
| | | | | | 26 | | | | | 26 | | EACH | LIGHT POLE | 679.45 | - | | | |
| | | | | | 1 | | | | | 1 | | EACH | POWER DROP STANCHION, STREET LIGHTING | 679.55 | - | | | |
| | | | | | 1 | | | | | 1 | | LU | PRICE ADJUSTMENT, FUEL (N.A.B.I.) | 690.50 | - | | | |
| | | | | | 10 | | | | | 10 | | CY | SPECIAL PROVISION (PERMANENT STONE CHECK DAM) | 900.608 | - | | | |
| | | | | | 4 | | | | | 4 | | EACH | SPECIAL PROVISION (BICYCLE RACK) | 900.620 | - | | | |
| | | | | | 26 | | | | | 26 | | EACH | SPECIAL PROVISION (LUMINAIRE, LED) (CMG PARK (31)) | 900.620 | - | | | |
| | | | | | 1 | | | | | 1 | | EACH | SPECIAL PROVISION (REMOVAL AND DISPOSAL OF EXISTING PAYPHONE) | 900.620 | - | | | |
| | | | | | 1 | | | | | 1 | | EACH | SPECIAL PROVISION (REMOVAL AND REPLACEMENT EXISTING FLUSHING BASIN IN PAVEMENT) | 900.620 | - | | | |
| | | | | | 1 | | | | | 1 | | EACH | SPECIAL PROVISION (REMOVAL OF EXISTING AREA LIGHTING SYSTEM) | 900.620 | - | | | |
| | | | | | 1 | | | | | 1 | | EACH | SPECIAL PROVISION (SOIL BEARING SLIP BASE) (2 1/2") | 900.620 | - | | | |
| | | | | | 700 | | | | | 700 | | LF | SPECIAL PROVISION (6 INCH UNDERDRAIN PIPE, DRY SWALE) | 900.640 | 10 | | | |
| | | | | | 60 | | | | | 60 | | LF | SPECIAL PROVISION (6 INCH UNDERDRAIN PIPE, DRY SWALE WITH STONE FILL) | 900.640 | 1 | | | |
| | | | | | 1 | | | | | 1 | | LS | SPECIAL PROVISION (BUS SHELTER) | 900.645 | - | | | |
| | | | | | 275 | | | | | 275 | | SY | SPECIAL PROVISION (STAMPED COLORED CONCRETE MEDIAN ISLAND, 5 INCH) | 900.675 | 24 | | | |
| | | | | | 150 | | | | | 150 | | SY | SPECIAL PROVISION (STAMPED COLORED CONCRETE TRAFFIC CIRCLE, 8 INCH) | 900.675 | 10 | | | |
| | | | | | 75 | | | | | 75 | | SY | SPECIAL PROVISION (UNIT BLOCK RETAINING WALL) | 900.675 | 5 | | | |

PROJECT NAME: RICHMOND
PROJECT NUMBER: CMG PARK (31)

FILE NAME: z97c186qty.dgn
PROJECT LEADER: ERIK ATKINS
DESIGNED BY: A. ACHARYA
QUANTITY SHEET #3

PLOT DATE: 5/14/2013
DRAWN BY: A. ACHARYA
CHECKED BY: T. BIGELOW
SHEET 100 OF 133