

STATE OF VERMONT AGENCY OF TRANSPORTATION												QUANTITY SHEET 1													
SUMMARY OF ESTIMATED QUANTITIES												TOTALS		DESCRIPTIONS						DETAILED SUMMARY OF QUANTITIES					
							ROADWAY	TRAINING	LANDSCAPING	EROSION CONTROL	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS					
							0.5					0.5		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10	-	COMMON EXCAVATION							
							1					1		EACH	DEMOLITION AND DISPOSAL OF BUILDING	202.10	-	5343 CY		PARK AND RIDE					
							5400					5400		CY	COMMON EXCAVATION	203.15	57	57 CY		ROUNDING					
							175					175		CY	SOLID ROCK EXCAVATION	203.16	15	5400 CY		TOTAL					
							350					350		CY	EARTH BORROW	203.30	2								
							2600					2600		CY	SAND BORROW	203.31	38								
							850					850		CY	TRENCH EXCAVATION OF EARTH	204.20	2								
							12					12		CY	TRENCH EXCAVATION OF ROCK	204.21	2								
							1					1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-								
							10					10		CY	STRUCTURE EXCAVATION	204.25	2								
							10					10		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30	2								
							2000					2000		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	92								
							25					25		CWT	EMULSIFIED ASPHALT	404.65	3								
							1					1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-								
							750					750		LB	BITUMINOUS CRACK SEALING	417.10	40								
							1450					1450		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	19								
							1					1		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-								
							1					1		LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-								
							2					2		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34	0.07								
							230					230		LB	REINFORCING STEEL, LEVEL I	507.11	6								
							1					1		EACH	PRECAST REINFORCED CONCRETE CATCH BASIN WITH CAST IRON GRATE	604.20	-								
							2					2		EACH	CAST IRON GRATE WITH FRAME, TYPE B	604.46	-								
							400					400		LF	6 INCH UNDERDRAIN PIPE	605.10	7								
							12					12		LF	6 INCH UNDERDRAIN CARRIER PIPE	605.20	1								
							11					11		EACH	UNDERDRAIN FLUSHING BASIN	605.95	-								
										450		450		MGAL	DUST CONTROL WITH WATER	609.10	EST.								
										5		5		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	EST.								
										50		50		CY	STONE FILL, TYPE I	613.10	3.4								
										50		50		CY	STONE FILL, TYPE II	613.11	3								
							975					975		LF	VERTICAL GRANITE CURB	616.21	24								
							1350					1350		LF	REMOVAL OF EXISTING CURB	616.41	50								
							75					75		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 8 INCH	618.11	3								
							11					11		EACH	YIELDING MARKER POSTS	619.17	-								
							125					125		LF	REMOVING AND RESETTING FENCE	620.50	6								
							2					2		EACH	ENERGY ABSORPTION ATTENUATOR	621.56	-								
							17					17		EACH	REMOVAL AND DISPOSAL OF GUIDE POSTS	621.81	-								
							250					250		LF	TEMPORARY TRAFFIC BARRIER	621.90	EST.								
							105					105		LF	DUCTILE IRON PIPE, CEMENT-LINED (18")	628.28	-								
											0.5	0.5		LS	FIELD OFFICE, ENGINEERS	631.10	-								
											0.5	0.5		LS	TESTING EQUIPMENT, CONCRETE	631.16	-								

PROJECT NAME: RICHMOND	
PROJECT NUMBER: CMG PARK (3I)	
FILE NAME: z97ci86qty.dgn	PLOT DATE: 4/30/2013
PROJECT LEADER: ERIK ATKINS	DRAWN BY: A. ACHARYA
DESIGNED BY: A. ACHARYA	CHECKED BY: T. BIGELOW
QUANTITY SHEET #1	SHEET 98 OF 133