



SURFACE/OVERLAY COURSE:	1-1/2" TYPE III (PLACED IN ONE LIFT)
BINDER COURSE :	3" TYPE II (PLACED IN ONE LIFT)
BASE COURSE:	4" TYPE I (PLACED IN ONE LIFT)
SUBBASE MATERIAL:	24" DENSE GRADED CRUSHED STONE (704.06)

- NOTES:
- CONTRACTOR SHALL MATCH EXISTING PAVEMENT THICKNESS IF GREATER THAN 8-1/2" AND AS DIRECTED BY THE ENGINEER, BY INCREASING TOTAL THICKNESS OF BASE COURSE PLACED IN TWO LIFTS INSTEAD OF ONE.
  - PERFORMANCE GRADED BINDER USED FOR THE BITUMINOUS CONCRETE PAVEMENT SHALL BE A PG 70-28

**PAVEMENT SCHEDULE**

NTS



**CONTRACT PLANS**

VERMONT AGENCY OF TRANSPORTATION

WILLISTON NHG 5500 (10)S "TAFT CORNERS" (US ROUTE 2 & VT ROUTE 2A)

WILLISTON VERMONT

**TYPICAL SECTIONS**

design RJD  
drawn JLC  
checked RJD  
scale NTS  
sht. no. 5

**LAMOUREUX & DICKINSON**  
Consulting Engineers Inc.  
14 Morse Drive  
Essex Junction, VT 05452  
(802) 878-4450  
Engineers-Planners-Surveyors