STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

ST. ALBANS CITY-ST. ALBANS STP 2204(I)S			ST. ALBANS CITY STP 9804(I)S		ST. ALBANS CITY STP 2129(I)S					
		ROADWAY	EMPLOYEE TRAINEE-SHIP	ROADWAY	EMPLOYEE TRAINEE-SHIP	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
		3		71		10	84	m^3	COMMON EXCAVATION	203.15	-
		2		21		6	29	m^3	SOLID ROCK EXCAVATION	203.16	-
		1					1	m^3	EARTH BORROW	203.30	
				1			1 *	m^3	TRENCH EXCAVATION OF EARTH (NOT A BID ITEM)	204.20	*
				1			1 *	m^3	TRENCH EXCAVATION OF ROCK	204.21	*
		3800		59100		9600	72500	m^2	COLD PLANING-BITUMINOUS PAVEMENT	210.10	-
				66		18	84	m^2	SCARIFYING PAVEMENT (MOD. 1)	212.20	-
				3		5	8	m^2	SCARIFYING PAVEMENT (MOD. 2)	212.20	-
		19		60		21	100	T	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.28	-
				1			1 *	T	AGGREGATE SHOULDERS	402.12	*
		350					350	T	AGGREGATE SHOULDERS (MOD.)	402.12	-
		3950		14200		2400	20550	KG	EMULSIFIED ASPHALT	404.65	-
		1550		7720		1300	10570	T	BITUMINOUS CONCRETE PAVEMENT (PG 58-34)	406.25	-
				1			1 *	LU	PRICE ADJUSTMENT ASPHALT CEMENT (NOT A BID ITEM)	406.50	*
				49		30	79	EA	CHANGING ELEVATION OF DI's, CB's, OR MH's	604.40	-
		7		119			126	EA	REHABILITATION OF DI'S, CB'S OR MH'S - CLASS I	604.412	-
				31		9	40	EA	CHANGING ELEVATION OF SEWER MANHOLES	604.42	-
				1			1	EA	CAST IRON GRATE WITH FRAME, TYPE D	604.47	-
		20		60		20	100	HR	POWER GRADER RENTAL	608.15	-
		40		60		20	120	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	-
		15		40		15	70	HR	POWER BROOM RENTAL	608.30	-
		10		60		20	90	HR	POWER BROOM RENTAL, TYPE II	608.31	-
		20		60		20	100	HR	TRUCK RENTAL	608.37	-
		20		60		20	100	HR	LOADER RENTAL, TYPE I	608.40	-
				6200		1700	7900	m^3	DUST CONTROL WITH WATER	609.10	-
		1		4		2	7	T	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	-
		10					10	m^3	STONE FILL, TYPE I	613.10	-
		1					1	M	VERTICAL GRANITE CURB	616.21	-
				509		26	535	M	CAST-IN-PLACE CEMENT CONCRETE CURB, TYPE B	616.28	-
		13					13	M	REMOVING AND RESETTING CURB	616.40	1
				149		26	175	M	REMOVAL OF EXISTING CURB	616.41	-
				11			11	T	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	-
		14		166		51	231	m^2	PORTLAND CEMENT CONCRETE SIDEWALK, 125 mm	618.10	-
				1		2	3	T	BITUMINOUS CONCRETE SIDEWALK	618.15	-
				136			136	M	STEEL BEAM GUARD RAIL	621.20	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

* THIS ITEM HAS BEEN LISTED ONLY ON THE STP 9804(I)S PROJECT, BUT SHALL BE SHARED ON THE ENTIRE CONTRACT.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME :
ST. ALBANS CITY
ST. ALBANS CITY-ST. ALBANS

PROJECT NO. :
STP 9804(I)S
STP 2129(I)S
STP 2204(I)S

DESIGN FILE NAME: /pave/97d150/pd150.dgn
IPARM FILE NAME: pd150cgl.i
SURVEYED BY: D-H
SQUAD LEADER: JLL
PLOT DATE: 01-FEB-2006 0
SURVEY DATE: 07/98
DRAWN BY: D-H
SHEET: 3 OF 105