STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

			EMPLOYEE TRAINEE-SHIP	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
					71	71	m³	COMMON EXCAVATION	203.15	2.1
					21	21	m³	SOLID ROCK EXCAVATION	203.16	1.2
					1	1	m³	TRENCH EXCAVATION OF EARTH (NOT A BID ITEM)	204.20	EST.
					1	1	m³	TRENCH EXCAVATION OF ROCK	204.21	EST.
					59100	59100	m²	COLD PLANING-BITUMINOUS PAVEMENT	210.10	1252
					66	66	m²	SCARIFYING PAVEMENT (MOD.1)	212.20	1.6
					3	3	m²	SCARIFYING PAVEMENT (MOD.2)	212.20	0.6
					60	60	T	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.28	1.1
					1	1	T	AGGREGATE SHOULDERS	402.12	EST.
					14200	14200	KG	EMULSIFIED ASPHALT	404.65	317
					7720	7720	T	BITUMINOUS CONCRETE PAVEMENT (PG 58-34)	406.25	149
					1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (NOT A BID ITEM)	406.50	EST.
					49	49	EA	CHANGING ELEVATION OF DI's, CB's, OR MH's	604.40	EST.
					119	119	EA	REHABILITATION OF DI'S, CB'S OR MH'S - CLASS I	604.412	EST.
					31	31	EA	CHANGING ELEVATION OF SEWER MANHOLES	604.42	EST.
					1	1	EA	CAST IRON GRATE WITH FRAME, TYPE D	604.47	EST.
					60	60	HR	POWER GRADER RENTAL	608.15	EST.
					60	60	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
					40	40	HR	POWER BROOM RENTAL	608.30	EST.
					60	60	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
					60	60	HR	TRUCK RENTAL	608.37	EST.
					60	60	HR	LOADER RENTAL, TYPE I	608.40	EST.
					6200	6200	m³	DUST CONTROL WITH WATER	609.10	156.9
					4	4	T	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	0.4
					509	509	M	CAST-IN-PLACE CEMENT CONCRETE CURB, TYPE B	616.28	7.5
					149	149	M	REMOVAL OF EXISTING CURB	616.41	3.0
					11	11	T	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	0.9
					166	166	m²	PORTLAND CEMENT CONCRETE SIDEWALK, 125 mm	618.10	3.3
					1	1	T	BITUMINOUS CONCRETE SIDEWALK	618.15	0.2
					136	136	M	STEEL BEAM GUARD RAIL	621.20	2.1

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
52966	m²	U.S. ROUTE 7 AREA
4882	m²	U.S. ROUTE 7 TOWN HIGHWAY AREA
1252	m²	ROUNDING
59100	m²	TOTAL
		BITUMINOUS CONCRETE PAVEMENT (PG 58-34)
5021	T	U.S. ROUTE 7 WEARING COURSE (TYPE IV)
463	T	TOWN HIGHWAY WEARING COURSE (TYPE IV)
31	T	DRIVES WEARING COURSE (TYPE IV)
1883	T	U.S. ROUTE 7 LEVELING COURSE (TYPE IV)
173	T	TOWN HIGHWAY LEVELING COURSE (TYPE IV)
149	T	ROUNDING
7720	T	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME : ST. ALBANS CITY

PROJECT NO. : STP 9804(I)S

DESIGN FILE NAME: /pave/97d150/pd150.dgn
IPARM FILE NAME: pd150gsl.i
SURVEYED BY: D-H
SQUAD LEADER: JLL
PLOT DATE: 01-FEB-2006 0
SURVEY DATE: 06/07/00
DRAWN BY: D-H
SHEET: 14 OF 105