KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUND-ATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
U.S. ROUTE 7																																				
2+082.3, LT		1	750	750	0.56						1			X		3.29 X																			E-152M	
		1	600	300	0.18																														65	
2+125.0, RT		1	750	750	0.56						1			X		2.90 X																		INSTALL POST USING SLEEVE AS DETAILED ON STANDARD E-12IM		E-145AM
2+142.0, LT.		1	750	750	0.56						1			X		3.29 X																				E-152M
		1	600	300	0.18																														65	
2+142.0, RT.		1	750	750	0.56						1			X		3.23 X																				E-152M
		1	600	300	0.18																														65	
2+145.8, LT.		1	750	750	0.56						1			X		2.93 X																		INSTALL POST USING SLEEVE AS DETAILED ON STANDARD E-12IM		E-143M
2+191.0, RT		1	750	750	0.56						1			X		2.96 X																		INSTALL POST USING SLEEVE AS DETAILED ON STANDARD E-12IM		E-143M
2+193.0, RT		1	750	750	0.56						1			X		3.29 X																		INSTALL NEW POST USING SLEEVE AS DETAILED ON STANDARD E-12IM		E-152M
		1	600	300	0.18																														65	
2+193.5, LT		1	750	750	0.56						1			X		3.29 X																		INSTALL NEW POST USING SLEEVE AS DETAILED ON STANDARD E-12IM		E-152M
		1	600	300	0.18																														65	
2+204.0, LT.		1	900	300	0.27						1			X		2.56 X																		NEW SIGNS SHALL BE MOUNTED USING MOUNTING BRACKET AS DETAILED ON STANDARD E-160M, IN SLEEVE AS DETAILED ON STANDARD E-12IM		E-142M
		1	900	300	0.27																															E-142M
2+303.0, RT.		1	750	750	0.56						1			X		2.90 X																				E-143M
TOTALS		m² 6.48		m²	EA.	m²						m 46.0 ~~46.0~~				m 46.0	m ~~46.0~~ 30.64	EA	kg			EA.	kg				EA.	EA.	kg						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: ST. ALBANS CITY
PROJECT NUMBER: STP 9804(I)S

FILE NAME: /pave/97dl50/pdl50.dgn
PROJECT LEADER: JLL
DESIGNED BY: D-H
IPARM FILE NAME: pdl50t10.i

PLOT DATE: 01-FEB-2006 07:5
DRAWN BY: D-H
CHECKED BY:
SHEET 57 OF 105