STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
U.S. ROUTE 7																																			
2+305.2, RT.		1	750	750	0.56						1			X		3.26 X																			E-152M
		1	600	300	0.18																													65	
2+305.2, LT.		1	750	750	0.56						1			X		3.29 X																	INSTALL POST USING SLEEVE AS DETAILED ON STANDARD E-121M		E-152M
		1	600	300	0.18																													65	
2+316.0, LT.	ONE WAY / ONE WAY	1	900	300	0.27						1			X		2.53 X																	INSTALL POST USING SLEEVE AS DETAILED ON STANDARD E-121M		E-142M
		1	900	300	0.27																														E-142M
2+377.0, LT.	STOP	1	750	750	0.56				1							2.93																	INSTALL NEW SIGN BACK TO BACK WITH EXISTING "DO NOT ENTER" SIGN ON EXISTING POST		E-143M
2+377.0, LT.	ONLY ONLY	1	900	750	0.68						1			X		2.96 X																			E-145AM
2+311.0, RT.		1	600	600	0.36											2.47 X																			
2+388.0, LT.	DO NOT ENTER B-B STOP	1	750	750	0.56		1				1			X		2.90 X																	MOUNT NEW STOP SIGN BACK TO BACK WITH SALVAGED DO NOT ENTER SIGN ON A NEW POST.	-	- E-143M
2+389.5, LT.	ONE WAY / ONE WAY	1	900	300	0.27		1				1			X		2.56 X																	SIGNS SHALL BE MOUNTED USING MOUNTING BRACKET AS DETAILED ON STANDARD E-160M	-	E-142M -
2+432.0, RT.		1	300	300	0.09						1			X		2.50 X																			E-143M
2+433.0, LT.		1	300	300	0.09						1			X		2.56 X																			E-143M
2+460.0, RT.	ONLY	1	750	750	0.56						1			X		2.93 X																			E-145AM
2+499.0, RT.		2	600	750	0.90						2			X		2.87 X																	INSTALL EACH NEW SIGN ASSEMBLY AT EITHER END OF EXISTING ISLAND USING SLEEVES AS DETAILED ON STANDARD E-121M		E-144M
		2	450	450	0.40																														E-150M
TOTALS			m² 6.13 6.49	m²	EA. 2	m²						m 50.6				m 50.6 33.76		EA		kg		EA.	kg				EA.	EA.	kg						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: ST. ALBANS CITY
PROJECT NUMBER: STP 9804(I)S

FILE NAME: /pave/97dl50/pdl50.dgn
PROJECT LEADER: JLL
DESIGNED BY: D-H
IPARM_FILE_NAME: pdl50tlll
PLOT DATE: 01-FEB-2006 07:5
DRAWN BY: D-H
CHECKED BY:
SHEET 58 OF 105