STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
U.S. ROUTE 7 3+034.0, RT.		1	750	750	0.56						1			X		3.41 X																				E-152M
		1	600	300	0.18																															65
3+034.0, RT.	STOP	1	750	750	0.56						1			X		2.90 X																				E-143M
3+040.8, RT.	RIGHT LANE ONLY / BIKE LANE	1	600	750	0.45						1			X		3.29 X																				66
		1	300	450	0.14																															66
3+070.0, RT.	TO NORTH INTERSTATE 89	1	600	300	0.18																															E-135M
		1	600	300	0.18						1			X		3.47 X																				E-135M
		1	600	600	0.36																															E-135M
3+110.0, LT.	RIGHT LANE ONLY / BIKE LANE	1	600	750	0.45						1			X		3.44 X																				66
		1	300	450	0.14																															66
3+120.0, RT.	RIGHT LANE ONLY / BIKE LANE	1	600	750	0.45						1			X		3.38 X																				66
		1	300	450	0.14																															66
3+137.0, LT.	REDUCED SPEED AHEAD	1	600	750	0.45						1			X		2.90 X																				E-142M
3+180.0, LT.	TO SOUTH INTERSTATE 89	1	600	300	0.18																															E-135M
		1	600	300	0.18						1			X		3.60 X																				E-135M
		1	600	600	0.36																															E-135M
												36.8				m 36.8	m		EA	kg	kg	kg		kg	kg	kg	kg							
TOTALS					m² 4.96	m²	EA.	m²				m ~~36.8~~				m ~~36.8~~ 26.39				kg			EA.	kg				EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: ST. ALBANS CITY
PROJECT NUMBER: STP 9804(I)S

FILE NAME: /pave/97d150/pd150.dgn
PROJECT LEADER: JLL
DESIGNED BY: D-H
IPARM_FILE_NAME: pd150t14.i
PLOT DATE: 01-FEB-2006 07:5
DRAWN BY: D-H
CHECKED BY:
SHEET 61 OF 105