STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
U.S. ROUTE 7 3+525.0, RT.	SHARE THE ROAD	1	750	750	0.56						1			X		3.53 X																			65	
		1	450	600	0.27																														65	
3+540.0, LT.	RIGHT LANE ONLY / NO BIKE LANE	1	600	750	0.45						1			X		3.29 X																			66	
		1	300	450	0.14																														66	
3+558.0, LT.	SPEED LIMIT 35	1	600	750	0.45						1			X		2.74 X																				E-142M
3+575.0, LT.	LANE AHEAD	1	600	750	0.45						1			X		2.90 X																			66	
3+589.0, LT.	ST. ALBANS CITY | ST. ALBANS TOWN	1	1500	190	0.29				1																								MOUNT NEW TOWN LINE SIGN ON EXISTING POST		E-124M
	SHEET 48 TOTALS				5.25		1							46.0		~~46.0~~ 31.68																			
	SHEET 49 TOTALS				3.96		2							36.8		~~36.8~~ 25.70																			
	SHEET 50 TOTALS				3.25		9							32.2		~~32.2~~ 26.40																			
	SHEET 51 TOTALS				4.76		2							46.0		~~46.0~~ 30.88																			
	SHEET 52 TOTALS				4.44		-							46.0		~~46.0~~ 28.99																			
	SHEET 53 TOTALS				3.86		1							64.4		~~64.4~~ 38.64																			
	SHEET 54 TOTALS				4.67		-							41.4		~~41.4~~ 27.28																			
	SHEET 55 TOTALS				~~10.51~~	9.77	1							27.6		~~27.6~~ 20.65																			
	SHEET 56 TOTALS				8.56		-							27.6		~~27.6~~ 17.68																			
	SHEET 57 TOTALS				6.48		-							46.0		~~46.0~~ 30.64																			
	SHEET 58 TOTALS				~~6.13~~	6.49	2							50.6		~~50.6~~ 33.76																			
	SHEET 59 TOTALS				2.95		2							41.4		~~41.4~~ 25.97																			
	SHEET 60 TOTALS				6.03		-							50.6		~~50.6~~ 32.40																			
	SHEET 61 TOTALS				4.96		-							36.8		~~36.8~~ 26.39																			
	SHEET 62 TOTALS				2.92		7							41.4		~~41.4~~ 27.48																			
	SHEET 63 TOTALS				2.61		-							18.4		~~18.4~~ 12.46																			
	SUBTOTALS				~~80.96~~ 81.34		27							653.2		~~653.2~~ 437.0																			
	ROUNDING				~~.09~~ 1.66		-							12.8		12.8																			
	TOTALS	~~83~~ m²				m²	27 EA.	m²			~~666~~ m					~~666~~ 437 m																			
											666 m					~~666~~ m	m		EA	kg	kg	kg		kg	kg	kg	kg							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: ST. ALBANS CITY
PROJECT NUMBER: STP 9804(I)S

FILE NAME: /pave/97dl50/pdl50.dgn
PROJECT LEADER: JLL
DESIGNED BY: D-H
IPARM_FILE_NAME: pdl50t16.i
PLOT DATE: 01-FEB-2006 07:5
DRAWN BY: D-H
CHECKED BY:
SHEET 63 OF 105