STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

				BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
					10	10	m³	COMMON EXCAVATION	203.15	0.6
					6	6	m³	SOLID ROCK EXCAVATION	203.16	0.9
					9600	9600	m²	COLD PLANING-BITUMINOUS PAVEMENT	210.10	188
					18	18	m²	SCARIFYING PAVEMENT (MOD. 1)	212.20	0.5
					5	5	m²	SCARIFYING PAVEMENT (MOD. 2)	212.20	0.4
					21	21	T	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.28	0.6
					2400	2400	KG	EMULSIFIED ASPHALT	404.65	141
					1300	1300	T	BITUMINOUS CONCRETE PAVEMENT (PG 58-34)	406.25	23
					30	30	EA	CHANGING ELEVATION OF DI's, CB's, OR MH's	604.40	EST.
					9	9	EA	CHANGING ELEVATION OF SEWER MANHOLES	604.42	EST.
					20	20	HR	POWER GRADER RENTAL	608.15	5
					20	20	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	5
					15	15	HR	POWER BROOM RENTAL	608.30	5
					20	20	HR	POWER BROOM RENTAL, TYPE II	608.31	5
					20	20	HR	TRUCK RENTAL	608.37	5
					20	20	HR	LOADER RENTAL, TYPE I	608.40	5
					1700	1700	m³	DUST CONTROL WITH WATER	609.10	53.4
					2	2	T	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	1
					26	26	M	CAST-IN-PLACE CEMENT CONCRETE CURB, TYPE B	616.28	0.9
					26	26	M	REMOVAL OF EXISTING CURB	616.41	0.9
					51	51	m²	PORTLAND CEMENT CONCRETE SIDEWALK, 125 mm	618.10	1.5
					2	2	T	BITUMINOUS CONCRETE SIDEWALK	618.15	0.9
					15	15	EA	ADJUST ELEVATION OF VALVE BOX	629.20	EST.
					700	700	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
					2000	2000	HR	FLAGGERS	630.15	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
8585	m²	VT ROUTE 36 AREA
827	m²	SIDEROADS
188	m²	ROUNDING
9600	m²	TOTAL
		BITUMINOUS CONCRETE PAVEMENT (PG 58-34)
814	T	VT ROUTE 36 WEARING COURSE (TYPE IV)
78	T	SIDE ROADS WEARING COURSE (TYPE IV)
51	T	DRIVES WEARING COURSE (TYPE IV)
305	T	VT ROUTE 36 LEVELING COURSE (TYPE IV)
29	T	TOWNHIGHWAY LEVELING COURSE (TYPE IV)
23	T	ROUNDING
1300	T	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME :
ST. ALBANS CITY

PROJECT NO. :
STP 2129(I)S

DESIGN FILE NAME: /pave/99d070/pd070.dgn
IPARM FILE NAME: pd070qsl.i
SURVEYED BY: D-H
SQUAD LEADER: D-H

PLOT DATE: 01-FEB-2006 0
SURVEY DATE: 09/98
DRAWN BY: D-H
SHEET: 72 OF 105