STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

				BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
					1	1	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
					1390	1390	M	DURABLE 100 mm WHITE LINE	646.40	26
					1950	1950	M	DURABLE 100 mm YELLOW LINE	646.41	36
					40	40	M	DURABLE 600 mm STOP BAR (TYPE I TAPE)	646.46	1.4
					58	58	EA	DURABLE LETTER OR SYMBOL (TYPE I TAPE)	646.50	-
					111	111	M	DURABLE CROSSWALK MARKING W/DIAGONAL LINES (MOD.)	646.51	2.8
					2840	2840	M	TEMPORARY 100 mm WHITE LINE	646.60	60
					3900	3900	M	TEMPORARY 100 mm YELLOW LINE	646.61	73
					80	80	M	TEMPORARY 600 mm STOP BAR	646.66	3
					84	84	EA	TEMPORARY LETTER OR SYMBOL	646.70	-
					230	230	M	TEMPORARY CROSSWALK MARKING W/DIAGONAL LINES	646.71	14
					90	90	EA	LINE STRIPING TARGETS	646.76	7
					85	85	M	PAINTED CURB	646.81	5
					10	10	KG	SEED	651.15	EST.
					60	60	KG	FERTILIZER	651.18	EST.
					0.5	0.5	T	AGRICULTURAL LIMESTONE	651.20	EST.
					0.5	0.5	T	HAY MULCH	651.25	EST.
					10	10	m^3	TOPSOIL	651.35	EST.
					22	22	m^2	TRAFFIC SIGNS, TYPE A	675.20	0.29
								BEGIN OPTION ITEM		
					174	174	M	FLANGED CHANNEL SIGN POSTS	675.301	3.8
					174	174	M	SQUARE TUBE SIGN POSTS AND ANCHOR	675.341	3.8
								END OPTION ITEM		
					64	64	EA	REMOVING SIGNS	675.50	-
					8	8	EA	ERECTING SALVAGED SIGNS	675.60	-
					88	88	M	VEHICLE DETECTOR LOOP	678.22	1.4
					4	4	M	WIRED CONDUIT (50 mm)	678.23	1
					1	1	EA	JUNCTION BOX	678.26	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME :

ST. ALBANS CITY

PROJECT NO. :

STP 2129(I)S

DESIGN FILE NAME: /pave/99d070/pd070.dgn
IPARM FILE NAME: pd070qs2.i
SURVEYED BY: D-H
SQUAD LEADER: D-H

PLOT DATE: 01-FEB-2006 0
SURVEY DATE: 09/98
DRAWN BY: D-H
SHEET: 73 OF 105