STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	NEW & SALVAGED SIGNS: SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	"A"	"B"	SALV SIGN	SALV TIS	EXIST POST: RETAIN	SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS						* ANCHOR = 1 METER																			
VT ROUTE 36	← BURLINGTON VT 28 RAILROAD STATION → SWANTON VT 9 → MONTREAL QUE →	1	1800	250	0.45																														E-123M
		1	1800	250	0.45																														E-123M
		1	1800	250	0.45																														E-123M
		1	1800	250	0.45																														E-123M
	SOUTH WEST NORTH 7 VERMONT 36 7 NO TURN ON RED	1	600	300	0.18																														E-136AM
		1	600	600	0.36																														E-136AM
		1	525	375	0.20																														E-136AM
I+420.6, LT.		1	600	600	0.36																														E-140M
																																INSTALL NEW SIGNS ON EXISTING WOOD FRAME		
		1	600	300	0.18																														E-136BM
		1	600	600	0.36																														E-136BM
		1	525	375	0.20																														E-136BM
		1	600	300	0.18																														E-136AM
		1	600	600	0.36																														E-136AM
		1	525	375	0.20																														E-136AM
I+451.0, LT.	ONLY ONLY	1	900	750	0.68						1			X		2.7 X		1.0																E-145AM
I+493.0, LT.	STOP 0360 0612 0093	1	750	750	0.56						1			X		2.7 X		1.0														BACK TO BACK.		E-143M
		1	150	200	0.03																														E-138M
I+495.1, RT.	EAST VERMONT 36 TO VERMONT 104																																INSTALL NEW SIGNS ON EXISTING WOOD FRAME		
		1	600	300	0.18																														E-136BM
		1	600	600	0.36																														E-136BM
		1	750	600	0.45																														E-136BM
I+505.0, RT.	STOP 0360 0612 0094	1	750	750	0.56						1			X		2.7 X		1.0														BACK TO BACK.		E-143M
		1	150	200	0.03																														E-138M
I+514.0, RT.		1	750	750	0.56						1			X		3.2 X		1.0																E-152M
		1	600	300	0.18																													88	
I+515.0, LT.		1	750	750	0.56						1			X		2.9 X		1.0																E-152M
		1	600	300	0.18																													88	
I+521.7, LT.	RESERVED PARKING	1	300	450	0.14						1			X		2.5 X		1.0																88	
TOTALS			m^2 9.03	m^2	EA.	m^2						m 27.6 ~~27.6~~				m 22.7 ~~27.6~~			EA	kg			EA.	kg				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT:	PROJECT NO.:
ST. ALBANS CITY	STP 2129(I)S

DESIGN FILE NAME: /pave/99d070/pd070.dgn
IPARM FILE NAME: pd070t01.i
SURVEYED BY: D-H
DESIGNED BY: D-H

PLOT DATE: 01-FEB-2006 0
SURVEY DATE: 09/98
DRAWN BY: D-H
SHEET: 83 OF 105