STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUND-ATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS							* ANCHOR = 1 METER																	
VT ROUTE 36 1+917.0, LT.		1	300	450	0.14				1																									MOUNT NEW SIGN ON EXISTING POST UNDER EXISTING SPEED LIMIT SIGN.	88	
1+935.7, LT.	BROWN AVE.						1				1			X		2.8 X		1.0																NEW STOP SIGN AND MILEMARKER MOUNTED BACK TO BACK. SALVAGED STREET SIGN INSTALLED 150 mm ABOVE THE 'STOP' SIGN USING POST TOP MOUNTING BRACKET ON NEW POST.	-	-
	STOP 0360 0612 0120	1	750	750	0.56																															E-143M
		1	150	200	0.03																															E-138M
2+036.5, RT.		1	750	750	0.56						1			X		3.3 X		1.0																		E-152M
		1	600	300	0.18																														88	
2+045.0, LT.		1	750	750	0.56						1			X		3.2 X		1.0																		E-152M
		1	600	300	0.18																														88	
2+050.2, RT.	FAIRFIELD ST. BARLOW ST.						1 1				1			X		2.7 X		1.0																NEW STOP SIGN AND MILEMARKER MOUNTED BACK TO BACK. SALVAGED STREET SIGNS INSTALLED 90° TO EACH OTHER, 150 mm ABOVE THE 'STOP' SIGNS USING POST TOP MOUNTING BRACKET ON NEW POST.	- -	- -
	STOP 0360 0612 0127	1	750	750	0.56																															E-143M
		1	150	200	0.03																															E-138M
2+086.0, LT.	SPEED LIMIT 25	1	600	750	0.45						1			X		3.2 X		1.0																		E-142M
		1	300	450	0.14																														88	
2+093.7, LT.	SMITH ST.						1				1			X		2.8 X		1.0																NEW STOP SIGN AND MILEMARKER MOUNTED BACK TO BACK. SALVAGED STREET SIGN INSTALLED 150 mm ABOVE THE 'STOP' SIGN USING POST TOP MOUNTING BRACKET ON NEW POST.	-	-
	STOP 0360 0612 0130	1	750	750	0.56																															E-143M
		1	150	200	0.03																															E-138M
2+183.7, LT.	BERKLEY TER.						1				1			X		2.8 X		1.0																NEW STOP SIGN AND MILEMARKER MOUNTED BACK TO BACK. SALVAGED STREET SIGN INSTALLED 150 mm ABOVE THE 'STOP' SIGN USING POST TOP MOUNTING BRACKET ON NEW POST.	-	-
	STOP 0360 0612 0136	1	750	750	0.56																															E-143M
		1	150	200	0.03																															E-138M
												m	m	m 32.2	m	m ~~32.2~~ 20.8	m	1.0	EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS			m^2 4.57	m^2	EA. 5	m^2						m ~~32.2~~			m ~~32.2~~ 27.8					kg			EA.	kg				EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: ST. ALBANS CITY	PROJECT NO.: STP 2129(1)S
DESIGN FILE NAME: /pave/99d070/pd070.dgn	
IPARM FILE NAME: pd070t04.i	PLOT DATE: 01-FEB-2006 0
SURVEYED BY: D-H	SURVEY DATE: 09/98
DESIGNED BY: D-H	DRAWN BY: D-H
	SHEET: 86 OF 105