STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS						* ANCHOR = 1 METER																			
VT ROUTE 36 2+188.7, LT.	NO OUTLET	1	750	750	0.56						1			X		3.0 X		1.0																		88	
2+232.0, RT.	R THIS SIDE OF STREET	1	300	450	0.14						1			X		2.4 X		1.0																		88	
2+317.4, LT.	SPEED LIMIT 25						1				1			X		3.0 X		1.0																SALVAGED SPEED LIMIT SIGN MOUNTED ABOVE NEW NO PARKING SIGN ON NEW POST.	-	-
	R THIS SIDE OF STREET	1	300	450	0.14																													88	
2+375.2, RT.	R THIS SIDE OF STREET	1	300	450	0.14						1			X		2.5 X		1.0																		88	
	TOTALS				0.98		1									10.9		4.0																			
																	14.9																			
	SHEET 83 TOTALS				9.03		-							27.6		~~27.6~~	22.7																			
	SHEET 84 TOTALS				2.87		-							46.0		~~46.0~~	37.1																			
	SHEET 85 TOTALS				4.26		2							46.0		~~46.0~~	38.8																			
	SHEET 86 TOTALS				4.57		5							32.2		~~32.2~~	27.8																			
	SHEET 87 TOTALS				0.98		1							18.4		~~18.4~~	14.9																			
	SUBTOTALS				21.71		8							170.2		~~170.2~~	141.3																			
	ROUNDING				~~0.29~~ 0		-							3.8		~~3.8~~	0																			
												m	m	m 174	m	m ~~174~~ 141.3	m		EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS					m^2 ~~22~~ 21.71	m^2	EA. 8	m^2				m ~~174~~			m ~~174~~ 141.3					kg	EA.	kg		EA.	EA.	kg											

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT:	PROJECT NO.:
ST. ALBANS CITY	STP 2129(I)S

DESIGN FILE NAME: /pave/99d070/pd070.dgn
IPARM FILE NAME: pd070t05.i
SURVEYED BY: D-H
DESIGNED BY: D-H
PLOT DATE: 01-FEB-2006 0
SURVEY DATE: 09/98
DRAWN BY: D-H
SHEET: 87 OF 105