STATE OF VERMONT
AGENCY OF TRANSPORTATION

# QUANTITY SHEET

VAOT Metric

## SUMMARY OF ESTIMATED QUANTITIES

| ROADWAY | QUANTITIES GRAND TOTAL | UNIT | ITEMS | ITEM NUMBER | RND |
|---|---|---|---|---|---|
| 3 | 3 | m³ | COMMON EXCAVATION | 203.15 | EST. |
| 2 | 2 | m³ | SOLID ROCK EXCAVATION | 203.16 | EST. |
| 1 | 1 | m³ | EARTH BORROW | 203.30 | EST. |
| 3800 | 3800 | m² | COLD PLANING - BITUMINOUS PAVEMENT | 210.10 | 57 |
| 19 | 19 | T | SUBBASE OF CRUSHED GRAVEL (FINE GRADED) | 301.28 | EST. |
| 350 | 350 | T | AGGREGATE SHOULDERS (MOD.) | 402.12 | 8 |
| 3950 | 3950 | KG | EMULSIFIED ASPHALT | 404.65 | 34 |
| 1550 | 1550 | T | BITUMINOUS CONCRETE PAVEMENT (PG 58-34) | 406.25 | 3 |
| 7 | 7 | EA | REHABILITATION OF DI'S, CB'S OR MH'S - CLASS I | 604.412 | EST. |
| 20 | 20 | HR | POWER GRADER RENTAL | 608.15 | EST. |
| 40 | 40 | HR | ALL PURPOSE EXCAVATOR RENTAL, TYPE I | 608.25 | EST. |
| 15 | 15 | HR | POWER BROOM RENTAL | 608.30 | EST. |
| 10 | 10 | HR | POWER BROOM RENTAL, TYPE II | 608.31 | EST. |
| 20 | 20 | HR | TRUCK RENTAL | 608.37 | EST. |
| 20 | 20 | HR | LOADER RENTAL, TYPE I | 608.40 | EST. |
| 1 | 1 | T | DUST AND ICE CONTROL WITH CALCIUM CHLORIDE | 609.15 | 0.8 |
| 10 | 10 | m³ | STONE FILL, TYPE I | 613.10 | EST. |
| 1 | 1 | M | VERTICAL GRANITE CURB | 616.21 | EST. |
| 13 | 13 | M | REMOVING AND RESETTING CURB | 616.40 | 1.0 |
| 14 | 14 | m² | PORTLAND CEMENT CONCRETE SIDEWALK, 125 mm | 618.10 | 0.5 |
| 1 | 1 | EA | ADJUST ELEVATION OF VALVE BOXES | 629.20 | EST. |
| 70 | 70 | HR | UNIFORMED TRAFFIC OFFICERS | 630.10 | EST. |
| 110 | 110 | HR | FLAGGERS | 630.15 | EST. |

## DETAILED SUMMARY OF QUANTITIES

| QUANTITIES | UNIT | ITEMS |
|---|---|---|
| | | COLD PLANING - BITUMINOUS PAVEMENT |
| 2950 | m² | MAINLINE |
| 396 | m² | TRANSITION |
| 397 | m² | APPROACH |
| 57 | m² | ROUNDING |
| 3800 | m² | TOTAL |
| | | BITUMINOUS CONCRETE PAVEMENT (PG 58-34) |
| 967 | T | MAINLINE WEARING COURSE (TYPE IV) |
| 580 | T | LEVELING COURSE (TYPE IV) |
| 3 | T | ROUNDING |
| 1550 | T | TOTAL |

## DETAILED SUMMARY OF QUANTITIES

| QUANTITIES | UNIT | ITEMS |
|---|---|---|

PROJECT NAME :
ST. ALBANS CITY
- ST. ALBANS

PROJECT NO. :
STP 2204(I)S

DESIGN FILE NAME: /pave/99bl60/pbl60.dgn
IPARM FILE NAME: pbl60ql.i
SURVEYED BY: D-H
SQUAD LEADER: JLL

PLOT DATE: 01-FEB-2006 0
SURVEY DATE: 04/17/00
DRAWN BY: D-H
SHEET: 93 OF 105