STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
780 STA 4+~~620~~.00 RT	NORTH EAST VERMONT 14 2	2 2 2	24 24 21	12 24 15	4.00 8.00 4.38						2	330"				X		X																#1	M3-1 M1-4 M5-1, M6-3		E-136A E-136B
STA 4+676.91 RT	← E. MONTPELIER ELEM. SCHOOL	1	72	20	10.0						2	321"				X		X																		
STA 4+690.00 RT	25 MPH	1 1	36 18	36 18	9.00 2.25						2	330"				X		X																	W3-3 W13-1		E-152 E-155
STA 4+694.48 LT	WEST SOUTH 2 VERMONT 14	2 2	24 24	12 24	4.00 8.00						2	327"				X		X																#1	M3-3, M3-4 M1-4		E-136A E-136B
STA 4+755.00 RT	ONLY	1	30	30	6.25						1	162"				X		X																	VR-921		E-145A
STA 4+752.50 LT.	E. MONTPELIER → ELEM. SCHOOL	1					1			2																										E-123
75 STA 4+~~780~~.00 LT	WEST SOUTH 2 VERMONT 14	2 2	24 24	12 24	4.00 8.00						2	341"				X		X																#1	M3-3, M3-4 M1-4		E-136A E-136B
MAST ARM #2	LEFT TURN YIELD ON GREEN	1	24	30	5.00																														LEFT TURN YIELD ON GREEN SIGN, MUTCD R10-12 SHALL BE MOUNTED ON MAST ARM 21 FOR LEFT TURNING TRAFFIC ON US ROUTE 2		
STA 4+830.00 RT	EAST 2 0020 1207 0300	1 1 1	24 24 6	12 24 8	2.00 4.00 0.33						1	159"				X		X																	M3-2 M1-4 INSTALLED, REMOVED, THEN SALVAGED TO 5+060 RT		E-136A E-136A E-138
STA 4+830.00 LT	WEST SOUTH NORTH 2 VERMONT 14 VERMONT 14	3 3 3	24 24 21	12 24 15	6.00 12.00 6.57						2	351"				X		X																#2	M3-4 M1-4 M6-3		E-136A E-136B
STA 4+890.00 LT	BARRE 5 MONTPELIER 7 N. MONTPELIER 3 → HARDWICK 20 →	4	72	10	20.0						2	335"				X		X																			E-123
STA 4+778 RT (& 4+830 RT)							1 (+1)			1 (+1)																								FIRE TRUCK (SYMBOL) SIGN INSTALLED - THEN R&S'ED TO STA. 4+830 RT		
												m	m	m	m	m 73.2	m		EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS					m2 ~~11.51~~ 123.78	m2	EA. + 3	m2				m			m 73.2					kg			EA.	kg				EA.	EA.	kg						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: EAST MONTPELIER
PROJECT NUMBER: STPG 028 - 3(35)S

FILE NAME: t98b028tsss.dgn
PROJECT LEADER: J. SCHULTZ
DESIGNED BY: J. GRUCHACZ
TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 22-MAR-2010
DRAWN BY: D. LYMAN
CHECKED BY: J. DEVLIN
SHEET 83 OF 142