STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) 44 kg/m 3.4	SQUARE STEEL (mm) 50 kg/m 3.9	SQUARE STEEL (mm) 63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	TUBULAR ALUMINUM Ø (mm) 100 kg/m 2.5	TUBULAR ALUMINUM Ø (mm) 100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	TUBULAR STEEL Ø (mm) 89 kg/m 13.4	TUBULAR STEEL Ø (mm) 100 kg/m 16.1	TUBULAR STEEL Ø (mm) 125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
											OPTION ITEMS																									
STA 14+155.00 RT.	NORTH VERMONT 14	1 1					1 1			1																							M3-1 M1-4		E-136B E-136B
STA 14+190.00 LT	25 M.P.H.	1 1	36 18	36 18	9.00 2.25						2	336"				X		X															W3-3 W13-1		E-152 E-155
STA 14+250.00 LT	JCT 2	1 1					1 1			1																							M2-1 M1-4		E-136A E-136A
STA 14+~~650~~ 228.00 LT APPROX.	TIS TIS	1 1						1 1		2																							RETAINED		E-125
STA 30+011.53 LT	KELTON RD STOP	1 1	30 30	12 30	2.50 6.25						1	175"				X		X															RI-1		E-123 E-143
STA 30+035.00 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1					1			1																							VR-017		E-141
STA 100+008.92 LT.	STOP	1					1			1																							RI-1		E-143
STA 100+097.03 RT	RESERVED PARKING	1	12	18	1.50						1	132"				X		X															R7-8		
STA 100+102.53 RT	RESERVED PARKING VAN ACCESSIBLE	1 1	12 12	18 6	1.50 0.50						1	132"				X		X															R7-8 R7-8A		
	TSSS 1 TOTALS				11.51		~~1~~ 3			2						73.2																				
	TSSS 2 TOTALS				5.40		~~12~~ 15			6						41.2																				
	TSSS 3 TOTALS				2.18		6	2		6						22.9																				
											m	m	m	m	m 137.3	m		EA	kg	kg	kg		kg	kg	kg	kg								
	TOTALS				m² 19.09 23.5 SF	m²	EA. ~~19~~ 24	EA. 2			m			m 137.3				kg			EA.		kg			EA.	EA.	kg							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: EAST MONTPELIER
PROJECT NUMBER: STPG 028 - 3(35)S

FILE NAME: t98b028tsss.dgn
PROJECT LEADER: J. SCHULTZ
DESIGNED BY: J. GRUCHACZ
TRAFFIC SIGN SUMMARY SHEET 3

PLOT DATE: 22-MAR-2010
DRAWN BY: D. LYMAN
CHECKED BY: J. DEVLIN
SHEET 85 OF 142