STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

VAST Metric

APPROXIMATE SUMMARY OF QUANTITIES

R.O.W.	EMPLOYEE TRAINEESHIP	NON-GOV'T PARTICIPATING	GOV'T PARTICIPATING BRIDGE	GOV'T PARTICIPATING ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
				5	5	T	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	EST
				150	150	m^3	STONE FILL, TYPE 1	613.10	--
				240	240	M	TREATED TIMBER CURB	616.35	4
				180	180	T	BITUMINOUS CONC. GUTTERS & TRAFFIC ISLANDS	616.47	--
				7	7	EA	RELOCATE MAIL BOX, SINGLE SUPPORT	617.10	EST
				1	1	EA	RELOCATE MAIL BOX, MULTIPLE SUPPORT	617.12	EST
				50	50	EA	YIELDING MARKER POSTS	619.17	EST
				1,400	1,400	M	STEEL BEAM GUARD RAIL (GALVANIZED)	621.20	51
				3,100	3,100	M	S.B.G.R. (GALVANIZED)(MOD. - W/2.4M POSTS)	621.20	105.6
				90	90	M	H.D. STEEL BEAM GUARD RAIL (GALVANIZED)	621.21	4.5
				60	60	EA	MANUFACTURED TERMINAL SECTION (FLARED)	621.505	--
				12	12	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	--
				4	4	EA	GUARD RAIL APPROACH SECTION, TYPE II	621.71	--
				4,600	4,600	M	REMOVAL AND DISPOSAL OF GUARD RAIL	621.80	14.7
				2	2	EA	REMOVAL AND DISPOSAL OF GUIDE POSTS	621.81	--
		6			6	EA	ADJUST ELEVATION OF VALVE BOX	629.20	--
				3,000	3,000	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
				7,500	7,500	HR	FLAGGERS	630.15	EST
			C & E	1	1	LS	FIELD OFFICE - ENGINEERS	631.10	--
			C & E	1	1	LS	TESTING EQUIPMENT - CONCRETE	631.16	--
			C & E	1	1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	--
			C & E	1	1	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	EST
	1040				1040	HR	EMPLOYEE TRAINEESHIP	634.10	EST
				1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	EST
				1	1	LS	TRAFFIC CONTROL	641.10	EST
				1	1	LS	PUBLIC RELATIONS OFFICER	641.12	EST
				2	2	LS	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	EST
				26,000	26,000	M	DURABLE 100 MM WHITE LINE (THERMOPLASTIC)	646.40	--
				25,000	25,000	M	DURABLE 100 MM YELLOW LINE (THERMOPLASTIC)	646.41	--
				150	150	M	DURABLE 200 MM WHITE LINE (THERMOPLASTIC)	646.42	50
				60	60	M	DURABLE 600 MM STOP BAR (THERMOPLASTIC)	646.46	--
				45	45	EA	DURABLE LETTER OR SYMBOL (THERMOPLASTIC)	646.50	--
				52,000	52,000	M	TEMPORARY 100 MM WHITE LINE	646.60	EST
				50,000	50,000	M	TEMPORARY 100 MM YELLOW LINE	646.61	EST
				150	150	M	TEMPORARY 200 MM WHITE LINE	646.62	EST
				120	120	M	TEMPORARY 600 MM STOP BAR	646.66	EST
				90	90	EA	TEMPORARY LETTER OR SYMBOL	646.70	--
				1,500	1,500	EA	LINE STRIPING TARGETS	646.76	EST
				350	350	M^2	GEOTEXTILE UNDER STONE FILL	649.31	--
				500	500	M^2	GEOTEXTILE FOR SILT FENCE	649.51	EST

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS			EQUATIONS +	EQUATIONS -	meters	kilometers	REMARKS

TOTALS

/pave/98b090/pb090.dgn pb090qs2.1

QUANTITY SHEET #2

PROJECT NAME **MARSHFIELD - CABOT**
PROJECT NUMBER **NH 2104(1)S**

DATE PLOTTED 09-MAY-2008
SHEET **6** OF **60** SHEETS