STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET NO. 3

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) kg/m 44 3.4	SQUARE STEEL (mm) kg/m 50 3.9	SQUARE STEEL (mm) kg/m 63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	TUBULAR ALUMINUM Ø (mm) kg/m 100 2.5	TUBULAR ALUMINUM Ø (mm) kg/m 100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	TUBULAR STEEL Ø (mm) kg/m 89 13.4	TUBULAR STEEL Ø (mm) kg/m 100 16.1	TUBULAR STEEL Ø (mm) kg/m 125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
															OPTION ITEMS																							
2+876 LT	STOP 0020 1209 0179	1 1	750 150	750 200	0.56 0.03						1			X		X																		BACK - TO - BACK		E-143M E-138M
2+886 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X		X																		REFER TO STANDARD E-121M FOR PLACEMENT.		E-141M
3+043 LT	T.I.C.S.							0.72																												E-125M
3+061 RT	TWINFIELD UNION SCHOOL →	1	1800	500	0.90						2			X		X																				E-123M
3+138 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X		X																		REFER TO STANDARD E-121M FOR PLACEMENT.		E-141M
	SPEED LIMIT 25	1	600	750	0.45																														E-142M
3+148 RT	STOP 0020 1209 0195	1 1	750 150	750 200	0.56 0.03						1			X		X																		BACK - TO - BACK		E-143M E-138M
3+178 RT	BRIDGE 77 US-2	1	150	200	0.03						1		X		X																					E-134M
3+185 LT	BRIDGE 77 US-2	1	150	200	0.03						1		X		X																					E-134M
3+219 LT	0020 1209 0200	1	150	200	0.03						1		X		X																					E-138M
3+255 LT	TWINFIELD UNION SCHOOL →	1	1800	500	0.90						2			X		X																				E-123M
3+320 RT	HIDDEN DRIVES	1	750	750	0.56						1			X		X																				E-154M
3+362 LT	WATCH FOR TURNING VEHICLES	1	900	900	0.81						2			X		X																				E-154M
3+362 RT	WATCH FOR TURNING VEHICLES	1	900	900	0.81						2			X		X																				E-154M
			m 2	m 2	EA.	m 2						m	m 8.1	m 59.8	m 8.1	m 59.8	m		EA.	kg	kg	kg	EA.	kg	kg	kg	kg	EA.	EA.	kg					
													67.9		67.9																				
	SHEET TOTALS		6.60			0.72																													

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: **MARSHFIELD - CABOT**
PROJECT NO.: **NH 2104(1)S**
DATE: 7-02

DESIGN FILE NAME: /pave/98b090/pb090.dgn
IPARM FILE NAME: pb090t03.1
SURVEYED BY:
SQUAD LEADER:

PLOT DATE: 09-MAY-2008 10:0
SURVEY DATE:
DRAWN BY: C.E.A., INC.
SHEET: **33** OF **60**