STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET NO. 6

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
																																		OPTION ITEMS		
7+287 RT		1	750	750	0.56						1			X		X																		50	
		1	600	450	0.27																														E-152M
7+298 LT		1 1	750 150	750 200	0.56 0.03						1			X		X																		BACK - TO - BACK		E-143M E-138M
7+308 LT		1	600	750	0.45						1			X		X																		REFER TO STANDARD E-121M FOR PLACEMENT.		E-141M
							1																											MOUNT SALVAGED SPEED LIMIT SIGN UNDER NEW LEGAL LOAD LIMIT SIGN		E-142M
7+364 RT		1	150	200	0.03						1		X			X																				E-134M
7+368 LT		1	150	200	0.03						1		X			X																				E-134M
7+400 LT		1	150	200	0.03						1		X			X																				E-138M
7+720 RT		1	150	200	0.03						1		X			X																				E-138M
8+047 RT		1	150	200	0.03						1		X			X																				E-138M
8+368 RT		1	150	200	0.03						1		X			X																				E-138M
8+758 RT		1	150	200	0.03						1		X			X																				E-134M
8+690 LT		1	150	200	0.03						1		X			X																				E-138M
9+012 RT		1	150	200	0.03						1		X			X																				E-138M
8+771 LT		1	150	200	0.03						1		X			X																				E-134M
			m 2	m 2	EA.	m 2						m	m 27.0	m 13.8	m 27.0	m 13.8	m		EA.	kg	kg	kg	EA.	kg	kg	kg	kg	EA.	EA.	kg					
	SHEET TOTALS		2.17		1								40.8			40.8																			

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: **MARSHFIELD - CABOT**
PROJECT NO.: **NH 2104(1)S**
DATE: 7-02

DESIGN FILE NAME: /pave/98b090/pb090.dgn
IPARM FILE NAME: pb090t06.i
SURVEYED BY:
SQUAD LEADER:
PLOT DATE: 09-MAY-2008 10:0
SURVEY DATE:
DRAWN BY: C.E.A., INC.
SHEET: **36** OF **60**