STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET NO. 9

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) kg/m 44 3.4	SQUARE STEEL (mm) kg/m 50 3.9	SQUARE STEEL (mm) kg/m 63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	TUBULAR ALUMINUM Ø (mm) kg/m 100 2.5	TUBULAR ALUMINUM Ø (mm) kg/m 100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	TUBULAR STEEL Ø (mm) kg/m 89 13.4	TUBULAR STEEL Ø (mm) kg/m 100 16.1	TUBULAR STEEL Ø (mm) kg/m 125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
														OPTION ITEMS																							
10+472 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X		X																		REFER TO STANDARD E-121M FOR PLACEMENT.		E-141M
	SPEED LIMIT 25	1	600	750	0.45																															E-142M
10+482 RT	STOP 0020 1209 0651	1 1	750 150	750 200	0.56 0.03						1			X		X																		BACK - TO - BACK		E-143M E-138M
10+498 LT	R	1	600	600	0.36						1			X		X																				E-143M
10+387 RT	R DEC 1 - APR 1 MIDNIGHT TO 7 AM	1	600	900	0.54						1			X		X																			49	
10+529 LT		1	750	750	0.56						1			X		X																				E-151M
	30 M. P. H.	1	450	450	0.20																															E-155M
10+575 LT	STOP	1	750	750	0.56						1			X		X																				E-143M
10+581 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X		X																		REFER TO STANDARD E-121M FOR PLACEMENT.		E-141M
10+587 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X		X																		REFER TO STANDARD E-121M FOR PLACEMENT.		E-141M
10+593 RT	STOP	1	750	750	0.56						1			X		X																				E-143M
10+613 RT	R	1	600	600	0.36						1			X		X																				E-143M
	BEGIN 0020 1209 0660	1 1	600 150	300 200	0.18 0.03																															E-140M E-138M
					m 2	m 2	EA.	m 2				m	m	m 46.0	m	m 46.0	m		EA.	kg	kg	kg	EA.	kg	kg	kg	kg	EA.	EA.	kg					
				SHEET TOTALS	5.74							46.0			46.0																						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: **MARSHFIELD - CABOT**
PROJECT NO.: **NH 2104(1)S**
DATE: 7-02

DESIGN FILE NAME: /pave/98b090/pb090.dgn
IPARM FILE NAME: pb090t09.i
SURVEYED BY:
SQUAD LEADER:
PLOT DATE: 09-MAY-2008 10:0
SURVEY DATE:
DRAWN BY: C.E.A., INC.
SHEET: **39** OF **60**