STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET NO. 14

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) kg/m 44	SQUARE STEEL (mm) kg/m 50	SQUARE STEEL (mm) kg/m 63	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75	TUBULAR ALUMINUM Ø (mm) kg/m 100	TUBULAR ALUMINUM Ø (mm) kg/m 100 MOD	TUBULAR STEEL FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75	TUBULAR STEEL Ø (mm) kg/m 89	TUBULAR STEEL Ø (mm) kg/m 100	TUBULAR STEEL Ø (mm) kg/m 125	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STD. SHEET NUMBER
												OPTION ITEMS																								
11+425 RT	TRUCK LANE 500 FEET	1	600	750	0.45						1			X		X																		E-141M
11+461 LT	SPEED LIMIT 35	1	600	750	0.45						1			X		X																		E-142M
11+462 RT	SPEED LIMIT 50	1	600	750	0.45						1			X		X																		E-142M
11+549 LT	MARSHFIELD PLAINFIELD 7	1	750	450	0.34						1			X		X																		E-128M
11+587 LT	0020 1209 0720	1	150	200	0.03						1		X		X																				E-138M
11+705 LT		1	900	900	0.81						2			X		X																		51	
11+709 LT	BRIDGE 82 US-2	1	150	200	0.03						1		X		X																				E-134M
11+709 RT	BRIDGE 82 US-2	1	150	200	0.03						1		X		X																				E-134M
11+756 RT	SLOWER TRAFFIC KEEP RIGHT	1	600	750	0.45						1			X		X																		E-141M
11+909 RT	0020 1209 0740	1	150	200	0.03						1		X		X																				E-138M
12+150 RT	SLOWER TRAFFIC KEEP RIGHT	1	600	750	0.45						1			X		X																		E-141M
			m 2	m 2	EA.	m 2						m	m 10.8	m 36.8	m 10.8	m 36.8	m	m	EA.	kg	kg	kg	EA.	kg	kg	kg	kg	EA.	EA.	kg					
	SHEET TOTALS		3.52										47.6			47.6																		

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: **MARSHFIELD – CABOT**
PROJECT NO.: **NH 2104(1)S**
DATE: 7-02

DESIGN FILE NAME: /pave/98b090/pb090.dgn
IPARM FILE NAME: pb090t14.1
SURVEYED BY:
SQUAD LEADER:
PLOT DATE: 09-MAY-2008 10:0
SURVEY DATE:
DRAWN BY: C.E.A., INC.
SHEET: **44** OF **60**