STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET NO. 18

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUND-ATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
12+866 LT	JCT	1	525	375	0.20						1			X		X																				E-136BM
	VERMONT 232	1	750	600	0.45																															E-136BM
12+915 LT		1	750	750	0.56						1			X		X																			51	
13+120 LT		1	750	750	0.56						1			X		X																			50	
13+168 RT	SHOULDER NARROWS	1	900	900	0.81						2			X		X																				E-151M
CABOT 0+000 RT	CABOT MARSHFIELD 0020 1209 0820	1	1500	200	0.30						2			X		X																				E-124M
		1	150	200	0.03																															E-138M
	0020 1204 0000	1	150	200	0.03																															E-138M
					m 2 2.94	m 2	EA.	m 2				m	m	m 32.2	m	m 32.2	m		EA.	kg	kg	kg	EA.	kg	kg	kg	kg	EA.	EA.	kg						

SHEET #31	1.81			2.88		32.7	32.7			
SHEET #32	5.74					56.0	56.0			
SHEET #33	6.60			0.72		67.9	67.9			
SHEET #34	3.94					51.1	51.1			
SHEET #35	3.32			1.44		31.1	31.1			
SHEET #36	2.17		1			40.8	40.8			
SHEET #37	4.77					46.8	46.8			
SHEET #38	4.68					56.0	56.0			
SHEET #39	5.74					46.0	46.0			
SHEET #40	5.73					46.0	46.0			
SHEET #41	4.54			2.16		36.8	36.8			
SHEET #42	6.71					46.0	46.0			
SHEET #43	4.05					32.2	32.2			
SHEET #44	3.52					47.6	47.6			
SHEET #45	4.70			2.16		39.5	39.5			
SHEET #46	6.26					44.1	44.1			
SHEET #47	4.81					36.8	36.8			
SHEET #48	2.94					32.2	32.2			
SUBTOTALS	82.03		1	9.36		789.6	789.6			
ROUNDING	2.97		--	0.64		10.4	10.4			
TOTALS	85.00		1	10.00		800.0	800.0			

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: **MARSHFIELD - CABOT**
PROJECT NO.: **NH 2104(1)S**
DATE: 7-02

DESIGN FILE NAME: /pave/98b090/pb090.dgn
IPARM FILE NAME: pb090t18.i
SURVEYED BY:
SQUAD LEADER:

PLOT DATE: 09-MAY-2008 10:0
SURVEY DATE:
DRAWN BY: C.E.A., INC.
SHEET: **48** OF **60**