STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 45 2.8	51 3.2	64 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 12.8	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
														OPTION ITEMS																								
0+000.0, LT	DANBY | WALLINGFORD 0070 1106 0247	1	1500	190	0.29						1			4.26																					SIGN ID CODE VD-700		E-124
		1	150	250	0.04									X		X		X																SIGN ID CODE VD-700		E-138
	0070 1125 0000	1	150	250	0.04																													SIGN ID CODE VD-700		E-138
0+321.9, RT	0070 1125 0020	1	150	250	0.04						1	2.74			X			X																SIGN ID CODE VD-700		E-138
0+501.0, LT	STOP 0070 1125 0032	1	750	750	0.56						1			3.96																					BACK-TO-BACK		
		1	150	250	0.04									X		X		X																SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
0+512.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X	4.26	X		X																SIGN ID CODE VR-017		E-141
	SPEED LIMIT 25						1																											SALVAGED EXISTING "SPEED LIMIT 25 MPH" SIGN		
0+523.0, RT	BRIDGE 70 US 7	1	150	200	0.03						1	2.72			X			X																SIGN ID CODE VD-701		E-134
0+532.0, LT	BRIDGE 70 US 7	1	150	200	0.03						1	2.43			X			X																SIGN ID CODE VD-701		E-134
0+643.7, LT	0070 1125 0040	1	150	250	0.03						1	2.43			X			X																SIGN ID CODE VD-700		E-138
0+965.6, RT	0070 1125 0060	1	150	250	0.04						1	2.43			X			X																SIGN ID CODE VD-700		E-138
1+263.0, LT	TRUCKS ENTERING	1	750	750	0.56						1			4.26		X		X																SIGN ID CODE WII-10		E-154
		m	m	m	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg																		
		12.77 ~~23.0~~		16.74 ~~18.4~~	23.0	18.4																														
TOTALS		m^2 2.61 ~~2.15~~	m^2	EA 1	m^2		m 29.51 ~~41.4~~		m 41.4	kg	EA	kg		EA	EA	kg																					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

PROJECT:	PROJECT NO.:
WALLINGFORD	NH 2108(1)S & STP EH04(6)

DESIGN FILE NAME: /pave/98b098/pb098.dgn
IPARM FILE NAME: pb098tssl.i
SURVEYED BY: N/A
SQUAD LEADER: D.E.G.
PLOT DATE: 8/05
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 54 OF 110