STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) 45 kg/m 2.8	SQUARE STEEL (mm) 51 kg/m 3.2	SQUARE STEEL (mm) 64 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	TUBULAR ALUMINUM Ø (mm) 100 kg/m 2.5	TUBULAR ALUMINUM Ø (mm) 100 MOD kg/m 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	TUBULAR STEEL Ø (mm) 89 kg/m 12.8	TUBULAR STEEL Ø (mm) 100 kg/m 16.1	TUBULAR STEEL Ø (mm) 125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																									
I+289.0, RT	0070 1125 0080	I	I50	250	0.04						I	2.43 X			X			X																	SIGN ID CODE VD-700		E-I38
I+364.0, RT	R1-1 STOP AHEAD SPEED LIMIT 40	I	900	900	0.8I						2			3.96 X 3.96		X		X																	SIGN ID CODE W3-5	78	
I+424.0, RT	SOUTH WALLINGFORD WALLINGFORD 4	I	750	450	0.34						I			3.65 X		X		X																	SIGN ID CODE WII-8		E-I28B
I+486.0, RT	SCHOOL BUS STOP AHEAD	I	750	750	0.56						I			4.26 X		X		X																	SIGN ID CODE S3-I		E-I53
I+56I.I, RT	SPEED LIMIT 40	I	600	750	0.45						I			4.26 X		X		X																	SIGN ID CODE R2-I		E-I42
I+56I.I, LT	SPEED LIMIT 50	I	600	750	0.45						I			4.26 X		X		X																	SIGN ID CODE R2-I		E-I42
I+609.0, RT	0070 1125 0100	I I	900 I50	900 250	0.8I 0.04						2			4.26 X 4.26																					SIGNS SHALL BE INSTALLED ON TWO FLANGED CHANNEL POSTS SIGN ID CODE WII-8 SIGN ID CODE VD-700	78	 E-I38
I+703.0, RT		I	750	750	0.56						I			4.26 X		X		X																	SIGN ID CODE W2-2M		E-I55
	HARTSBORO RD	I	I050	200	0.2I																														79	
														37.13																							
												m 2.43 4.6	m	m 36.8 (9.2)	m 4.6	m 36.8	m		EA	kg	kg	kg		kg	kg	kg	kg									
TOTALS			m^2 4.27	m^2	EA	m^2						m 39.56 4I.4 (9.2)			m 4I.4					kg	EA	kg						EA	EA	kg						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

PROJECT:	PROJECT NO.:
WALLINGFORD	NH 2108(I)S & STP EH04(6)

DESIGN FILE NAME: /pave/98b098/pb098.dgn
IPARM FILE NAME: pb098tss2.I
SURVEYED BY: N/A
SQUAD LEADER: D.E.G.
PLOT DATE: 8/05
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 55 OF II0