STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 45 kg/m 2.8	51 kg/m 3.2	64 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	75 kg/m 11.3	89 kg/m 12.8	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
2+700.0, LT	HIDDEN DRIVE LEFT	1	750	750	0.56						2 +			5.48 X 5.48			X	X																SIGN ID CODE VW-133		E-154
	SCHOOL BUS STOP AHEAD	1	750	750	0.56																													SIGN ID CODE S3-1		E-153
2+755.0, LT	SOUTH WALLINGFORD DANBY 4	1	750	450	0.34						1			4.26 X		X		X																	E-128A E-128B	
2+835.0, LT	SPEED LIMIT 40	1	900	900	0.81						2			3.96 X 4.26		X		X																SIGN ID CODE W3-5	78	
2+896.0, RT	0070 1125 0180	1	150	250	0.04						1	2.43 X			X			X																SIGN ID CODE VD-700		E-138
3+218.7, LT	0070 1125 0200	1	150	250	0.04						1	2.43 X			X			X																SIGN ID CODE VD-700		E-138
3+540.6, RT	0070 1125 0220	1	150	250	0.04						1	2.43 X			X			X																SIGN ID CODE VD-700		E-138
3+862.4, LT	0070 1125 0240	1	150	250	0.04						1	2.43 X			X			X																SIGN ID CODE VD-700		E-138
3+887.0, RT	BRIDGE 74 US 7	1	150	200	0.03						1	3.04 X			X			X																SIGN ID CODE VD-701		E-134
											m	m	m		m	m	m		EA	kg	kg	kg		kg	kg	kg	kg								
											~~23.0~~ 12.76		~~18.4~~ 23.44		23.0	13.8	4.6																		
TOTALS			m^2 2.46	m^2	EA	m^2					m ~~41.4~~ 36.2				m 41.4					kg			EA	kg				EA	EA	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

PROJECT:	PROJECT NO.:
WALLINGFORD	NH 2108(1)S & STP EH04(6)

DESIGN FILE NAME: /pave/98b098/pb098.dgn
IPARM FILE NAME: pb098tss5.i
SURVEYED BY: N/A
SQUAD LEADER: D.E.G.
PLOT DATE: 8/05
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 59 OF 110