STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 11

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 45 2.8	51 3.2	64 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 12.8	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
7+409.0, RT	BRIDGE 79 US 7	1	150	200	0.03						1	2.74 X			X			X																SIGN ID CODE VD-701		E-134
7+507.0, LT	BRIDGE 79 US 7	1	150	200	0.03						1	2.74 X			X			X																SIGN ID CODE VD-701		E-134
7+552.0, LT		1	750	750	0.56						1			4.57 X		X		X																SIGN ID CODE WI-10	78	
7+600.0, RT	BRIDGE 80 US 7	1	150	200	0.03						1	2.74 X			X			X																SIGN ID CODE VD-701		E-134
7+645.0, RT		1	750	750	0.56						2			X 5.49		X		X																SIGN ID CODE W2-2M		E-155
	SCHOOL BUS STOP AHEAD	1	750	750	0.56																													SIGN ID CODE S3-1		E-153
7+665.0, LT	BRIDGE 80 US 7	1	150	200	0.03						1	2.74 X			X			X																SIGN ID CODE VD-701		E-134
7+740.0, RT		1	900	900	0.81						2			4.57 X 4.87		X		X																	78	
7+810.0, RT	SHOULDER NARROWS	1	750	750	0.56						1			4.57 X		X		X																SIGN ID CODE W5-1		E-151
7+854.0, RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			3.96 X		X		X																SIGN ID CODE VR-017		E-141
7+859.0, RT	TIMBER HILL ESTATES TH 68						1				1			3.96 X		X		X																SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP 0070 1125 0488	1	750	750	0.56																													BACK-TO-BACK SIGN ID CODE RI-1		E-143
		1	150	250	0.04																													SIGN ID CODE VD-700		E-138
												m 10.96 ~~18.4~~	m	m 36.86 ~~36.8~~	m 18.4	m 36.8	m		EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS			m² 4.22	m²	EA 1	m²						m 47.82 ~~55.2~~			m 55.2					kg			EA	kg				EA	EA	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

PROJECT: WALLINGFORD

PROJECT NO.: NH 2108(1)S & STP EH04(6)

DESIGN FILE NAME: /pave/98b098/pb098.dgn
IPARM FILE NAME: pb098tss10.i
SURVEYED BY: N/A
SQUAD LEADER: D.E.G.
PLOT DATE: 8/05
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 64 OF 110