STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 16

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 45 kg/m 2.8	51 kg/m 3.2	64 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	89 kg/m 12.8	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
														OPTION ITEMS																								
8+639.0, RT	(R8-3A)	1	600	600	0.36						1			X 3.96		X		X																	SIGN ID CODE R8-3A		E-143
	11 P.M. - 7 A.M. NOV. 15 - APR. 1	1	600	250	0.15																															78	
8+675.0, RT	↑ CLARENDON 3	1	1800	250	0.45						2			4.26 X 4.26		X		X																	SIGN ID CODE D1-1A		80	
	↑ RUTLAND 10	1	1800	250	0.45																														SIGN ID CODE D1-1A		80	
	← TINMOUTH 5	1	1800	250	0.45																														SIGN ID CODE D1-1A		80	
	E WALLINGFORD 6 →	1	1800	250	0.45																														SIGN ID CODE D1-1A		80	
8+707.0, LT	SOUTH	1	600	300	0.18						1			3.96 X	—	FM KPL ~~X~~	—	~~X~~																	SIGN ID CODE M3-3		E-136A
	7	1	600	600	0.36																														SIGN ID CODE M1-4		E-136A
8+721 RT	VT 140 SIGN ASSEMBLY		—	—	—		6		1		—	—	—	—	—	—	—	—	—	—														REPAIRED BROKEN BRACKETS SUPPORTING THE VT 140 ASSEMBLY		
8+743.0, LT	DEPOT ST	1	600	200	~~0.12~~				—	—	+	—	~~X~~	—	—	~~X~~	—	—	~~X~~																SIGN ID CODE D-3		E-123
	NOT INSTALLED - EXISTING SIGNS RETAINED NEW SIGNS NOT COMPATIBLE WITH EXIST. CLAMPS																																		EXISTING SIGNS ON TOP OF PEDESTRIAN LIGHT POLES		
8+752.0, RT	SCHOOL ST	1	600	200	~~0.12~~				—	—	+	—	~~X~~	—	—	~~X~~	—	—	~~X~~																SIGN ID CODE D-3		E-123
8+800.0, RT	(R8-3A)	1	600	600	0.36						1			3.96 X		X		X																	SIGN ID CODE R8-3A		E-143
	END	1	600	300	0.18							—	—																						SIGN ID CODE M4-6		E-140
												m	m	m 20.4 ~~23.0~~	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg								
													9.2			32.2			2																	
TOTALS			m^2 3.39 3.63	m^2	EA 6	m^2						m 32.2			m 32.2					kg			EA	kg				EA	EA	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

PROJECT: WALLINGFORD
PROJECT NO.: NH 2108(1)S & STP EH04(6)

DESIGN FILE NAME: /pave/98b098/pb098.dgn
IPARM FILE NAME: pb098tssl4.i
SURVEYED BY: N/A
SQUAD LEADER: D.E.G.
PLOT DATE: 8/05
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 69 OF 110