STATE OF VERMONT

TRAFFIC SIGN SUMMARY SHEET 19

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) 45 kg/m 2.8	SQUARE STEEL (mm) 51 kg/m 3.2	SQUARE STEEL (mm) 64 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	TUBULAR ALUMINUM Ø (mm) 100 kg/m 2.5	TUBULAR ALUMINUM Ø (mm) 100 MOD kg/m 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	TUBULAR STEEL Ø (mm) 89 kg/m 12.8	TUBULAR STEEL Ø (mm) 100 kg/m 16.1	TUBULAR STEEL Ø (mm) 125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
														OPTION ITEMS																							
9+010.0, RT	LEGAL LOAD LIMIT 24,000 POUNDS / NO THRU TRUCKS	1	600	750	0.45		1				1			4.26 X		X		X																	"NO THRU TRUCKS" SIGN - SALVAGED SALVAGED "SPEED LIMIT 25" SIGN ID CODE VR-017		E-141
	SPEED LIMIT 25		—	—	—		1				1			3.65																						
9+025.0, RT	STOP / 0070 1125 0566	1 1	750 150	750 250	0.56 0.04						1			3.96 X		X		X																	BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700 SALVAGE "HULL AVE" SIGN		E-143 E-138
	HULL AVE						1																													
9+030.0, RT	R	1	600	600	0.36						1			3.96 X		X		X																	SIGN ID CODE R8-3A		E-143
	END	1	600	300	0.18																													SIGN ID CODE M4-6		E-140
9+082.0, LT	R	1	600	600	0.36						1			3.96 X		X		X																	SIGN ID CODE R8-3A		E-143
	11 P.M. - 7A.M. NOV. 15 - APR. 1	1	600	250	0.15																														78	
9+140.0, LT	R	1	600	600	0.36						1			4.26 X		X		X																	SIGN ID CODE R8-3A		E-143
	11 P.M. - 7A.M. NOV. 15 - APR. 1	1	600	250	0.15																														78	
	BEGIN	1	600	300	0.18																													SIGN ID CODE M4-11		E-140
9+155.0, LT	R	1	600	600	0.36						1			3.96 X		X		X																	SIGN ID CODE R8-3A		E-143
	END	1	600	300	0.18																													SIGN ID CODE M4-6		E-140
												m	m	m 28.01 ~~27.6~~	m	m 27.6	m		EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS					m² 3.33	m²	EA 3	m²				m ~~27.6~~ 28.01			m 27.6					kg	EA	kg		EA	EA	kg									

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

PROJECT: WALLINGFORD

PROJECT NO.: NH 2108(1)S & STP EH04(6)

DESIGN FILE NAME: /pave/98b098/pb098.dgn
IPARM FILE NAME: pb098tss16.i
SURVEYED BY: N/A
SQUAD LEADER: D.E.G.
PLOT DATE: 8/05
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 72 OF 110