STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 22

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 45 kg/m 2.8	51 3.2	64 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 2.5	100 MOD 2.5	FOUND-ATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	89 12.8	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
9+290.0, RT		1	600	600	0.36						1			4.26 X		X		X															SIGN ID CODE R8-3A		E-143
		1	600	250	0.15																														78	
		1	600	300	0.18																												SIGN ID CODE M4-6		E-140
9+291.0, LT		1	600	750	0.45						1			3.96 X		X		X															SIGN ID CODE VR-017		E-141
9+302.0, RT		1	600	750	0.45						1			3.96 X		X		X															SIGN ID CODE R2-1		E-142
9+302.0 LT		1	600	750	0.45						1			3.96 X		X		X															SIGN ID CODE R2-1		E-142
9+419.0, RT		1	600	300	0.18						1			4.26 X		X		X															SIGN ID CODE M3-1		E-136A
		1	600	600	0.36																												SIGN ID CODE M1-4		E-136A
9+625.0, RT		1	750	750	0.56									4.26																			SIGN ID CODE VW-060		E-154
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."												m	m	m 24.66 ~~23.0~~	m	m 23.0	m		EA	kg	kg	kg		kg	kg	kg	kg								
	TOTALS				m^2 3.14	m^2	EA 0	m^2						m 24.66 ~~23.0~~		m 23.0					kg		EA		kg			EA	EA	kg					

PROJECT:	PROJECT NO.:
WALLINGFORD	NH 2108(1)S & STP EH04(6)

DESIGN FILE NAME: /pave/98b098/pb098.dgn
IPARM FILE NAME: pb098tss19.i
SURVEYED BY: N/A
SQUAD LEADER: D.E.G.
PLOT DATE: 8/05
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 75 OF 110