STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 23

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) kg/m 45 2.8	SQUARE STEEL (mm) kg/m 51 3.2	SQUARE STEEL (mm) kg/m 64 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	TUBULAR ALUMINUM Ø (mm) kg/m 100 2.5	TUBULAR ALUMINUM Ø (mm) kg/m 100 MOD 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	TUBULAR STEEL Ø (mm) kg/m 89 12.8	TUBULAR STEEL Ø (mm) kg/m 100 16.1	TUBULAR STEEL Ø (mm) kg/m 125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
														OPTION ITEMS																								
9+860.0, RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			3.96 X		X		X																	SIGN ID CODE VR-017		E-141
9+871.0, LT	HIDDEN DRIVES	1	750	750	0.56						1			4.87 X 4.87			X	X																	SIGN ID CODE S3-1		E-153
	SCHOOL BUS STOP AHEAD	1	750	750	0.56																														SIGN ID CODE VW-060		E-154
9+871.0, RT	STOP 0070 1125 0609	1 1	750 150	750 250	0.56 0.04						1			3.96 X		X		X																	BACK-TO-BACK SIGN ID CODE R1-1 SIGN ID CODE VD-700		E-143 E-138
9+871.0, RT	NO OUTLET	1	750	750	0.56						1			4.26 X		X		X																	SIGN ID CODE W14-1	78	
9+961.0, LT	SPEED LIMIT 35	1	600	750	0.45						1			3.96 X		X		X																	SIGN ID CODE R2-1		E-142
9+961.0, RT	SPEED LIMIT 45	1	600	750	0.45						1			3.96 X		X		X																	SIGN ID CODE R2-1		E-142
9+977.9, RT	0070 1125 0620	1	150	250	0.04						1	2.74 X			X			X																	SIGN ID CODE VD-700		E-138
TOTALS		m² 3.67	m²	EA	m²							m 2.74 ~~4.6~~	m	m 29.84 ~~27.6~~ 32.58 ~~32.2~~	m 4.6	m 23.0	m 4.6		EA	kg	kg	kg	EA	kg	kg	kg	kg	EA	EA	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

PROJECT:	PROJECT NO.:
WALLINGFORD	NH 2108(1)S & STP EH04(6)

DESIGN FILE NAME: /pave/98b098/pb098.dgn
IPARM FILE NAME: pb098tss20.1
SURVEYED BY: N/A
SQUAD LEADER: D.E.G.
PLOT DATE: 8/05
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 76 OF 110