STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET 2

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

				EMPLOYEE TRAINEESHIP	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
						1077	1077	m	STEEL BEAM GUARDRAIL (GALVANIZED)	621.20	3
						30	30	m	STEEL BEAM GUARDRAIL (MOD-2.4 m POSTS)(GALVANIZED)	621.20	EST.
						40	40	m	HEAVY DUTY STEEL BEAM GUARDRAIL (GALVANIZED)	621.21	0
						28	28	EA	MANUFACTURED TERMINAL SECTION (FLARED)	621.505	0
						1	1	EA	MANUFACTURED TERMINAL SECTION (TANGENT)	621.505	EST
						2	2	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	0
						200	200	m	REMOVING AND RESET GUARDRAIL	621.75	EST.
						25	25	EA	REPLACE GUARDRAIL POST ASSEMBLY	621.76	EST.
						50	50	EA	REPLACE GUARDRAIL BEAM UNIT	621.77	EST.
						100	100	m	ADJUST HEIGHT OF GUARDRAIL	621.79	EST.
						1400	1400	m	REMOVL AND DISP. OF GUARDRAIL	621.80	1
						1	1	EA	REMOVL AND DISP. OF GUIDE POSTS	621.81	EST.
						690	690	HR	UNIFORMED TRAFFIC OFFICERS	630.10	10
						1030	1030	HR	FLAGGERS	630.15	10
						1	1	LS	FIELD OFFICE ENGINEERS	631.10	
						1	1	LS	TESTING EQUIPMENT - CONCRETE	631.16	-
						1	1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	-
						1	1	LU	FIELD OFFICE--TELEPHONE (NOT A BID ITEM)	631.25	
				520			520	HR	EMPLOYEE TRAINEESHIP	634.10	
						1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
						22700	22700	m	DURABLE 100 mm WHITE LINE (THERMOPLASTIC)	646.40	236
						22860	22860	m	DURABLE 100 mm YELLOW LINE (THERMOPLASTIC)	646.41	231
						85	85	m	DURABLE 600 mm STOP BAR (THERMOPLASTIC)	646.46	3
						40	40	EA	DURABLE LETTER OR SYMBOL (THERMOPLASTIC)	646.50	0
						22700	22700	m	TEMPORARY 100 mm WHITE LINE	646.60	236
						22860	22860	m	TEMPORARY 100 mm YELLOW LINE	646.61	231
						85	85	m	TEMPORARY 600 mm STOP BAR	646.66	3
						40	40	EA	TEMPORARY LETTERS OR SYMBOLS	646.70	0
						2870	2870	EA	LINE STRIPING TARGETS	646.76	31
						85	85	m2	GEOTEXTILE UNDER STONEFILL	649.31	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT : HARDWICK-GREENSBORO
PROJECT NO. : STP 2112(1)S

DESIGN FILE NAME: pave/98b106/pb106.dgn
IPARM FILE NAME: pb106qs02.i
PLOT DATE: 10-JUL-2006 13:49
SURVEYED BY: CLD ENGINEERS, INC.
SURVEY DATE: 6/99
SQUAD LEADER: WRH
DRAWN BY: JPC
SHEET: 6 OF 43