STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
STA 4+954 LT	BAYLEY-HAZEN RD						1				1			X		X																	SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP 0160 0305 0309	1 1	750 150	750<br~~200~~ 254	0.56 0.038																											BACK TO BACK		E-143M E-138M
STA 4+960 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X		X																			E-141M
STA 5+416 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X		X																			E-141M
STA 5+426 RT	MICHAUD FARM RD						1				1			X		X																	SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP 0160 0305 0337	1 1	750 150	750 254	0.56 0.038		~~1~~																									BACK TO BACK		E-143M
																																NEW			
STA 6+095 LT	DIMICK RD	1	230	610	0.14		~~1~~				1			X		X	X																~~SALVAGED~~ SIGN ~~TO BE~~ INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP 0160 0305 0379	1 1	750 150	750<br~~200~~ 254	0.56 0.038																											BACK TO BACK		E-143M E-138M
STA 6+105 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X		X																			E-141M
STA 6+827 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			X		X																			E-141M
STA 6+842 RT	STOP 0160 0305 0425	1 1	750 150	750<br~~200~~ 254	0.56 0.038						1			X		X																	BACK TO BACK		E-143M E-138M
GREENSBORO																																			
STA 0+045 LT	R & S STOP 0160 1009 0003	~~1~~ 1	~~750~~ 150	~~750~~ 254	~~0.56~~ 0.038		1 ~~1~~				1			X		X																	BACK TO BACK		E-143M
												m	m	41.4	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg							
TOTALS			~~4.37~~ 4.69	m²	EA. ~~3~~ 5	m²						m 41.4			m 41.4					kg	EA.	kg						EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT :	PROJECT NO. :
HARDWICK-GREENSBORO	STP 2112(1)S

DESIGN FILE NAME: pave/98b106/pb106.dgn
IPARM FILE NAME: pb106ts02.i
PLOT DATE: 10-JUL-2006 13
SURVEYED BY: CLD ENGINEERS, INC.
SURVEY DATE: 6/99
SQUAD LEADER: WRH
DRAWN BY: JPC
SHEET: 38 OF 43