QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			FULL E & C ITEMS	NON PARTICIPATING	EROSION CONTROL	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						1	1	LS	CLEARING AND GRUBBING (INCL. INDIV. TREES & STUMPS)	201.10	
						3840	3840	SY	COLD PLANING-BIT. PAVEMENT	210.10	-
						5	5	CWT	EMULSIFIED ASPHALT	404.65	-
						320	320	TON	BITUMINOUS CONCRETE PAVEMENT (P.G. 58-28)	406.25	-
						20	20	HR	ROADWAY PATROL MAINTENANCE	607.10	EST.
						480	480	HR	ALL PURP. EXCAVATOR RENTAL, TYPE II	608.26	EST.
						40	40	HR	POWER BROOM RENTAL	608.30	EST.
						960	960	HR	TRUCK RENTAL	608.37	EST.
						480	480	HR	LOADER RENTAL TYPE I	608.40	EST.
						480	480	HR	LOADER RENTAL TYPE II	608.41	EST.
						140	140	M/GAL	DUST CONTROL W/WATER	609.10	EST.
						1	1	TON	DUST AND ICE CONTROL W/CALC. CHLORIDE	609.15	EST.
					5		5	CY	STONE FILL TYPE I - (MOD - CHECK DAM)	613.10	EST.
					400		400	LF	SNOWFENCE	620.70	EST.
					685		685	LF	MISCELLANEOUS FENCE (MOD. - SEDIMENT LOG)	620.80	-
						2	2	EA	MANUFACTURED TERMINAL SECTION (TANGENT)	621.505	-
						3	3	EA	ENERGY ABSORPTION ATTENUATOR	621.56	-
						50	50	LF	REMOVAL AND DISPOSAL OF GUARD RAIL	621.80	
				1050			1050	LF	TEMPORARY TRAFFIC BARRIER (MOD.)	621.90	-
						200	200	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
						300	300	HR	FLAGGERS	630.15	EST.
			1				1	LS	FIELD OFFICE-ENGINEERS (MOD.)	631.10	-
			1				1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	-
			1				1	LU	FIELD OFFICE-TELEPHONE (N.A.B.I.)	631.25	-
						1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
						1	1	LS	TRAFFIC CONTROL	641.10	EST.
						3	3	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
						2450	2450	LF	DURABLE 4'' WHITE LINE (THERMOPLASTIC)	646.40	-
						2450	2450	LF	DURABLE 4'' YELLOW LINE (THERMOPLASTIC)	646.41	-
						3650	3650	LF	TEMPORARY 4'' WHITE LINE (PAINT)	646.60	-
						2550	2550	LF	TEMPORARY 4'' YELLOW LINE (PAINT)	646.61	-
						20	20	LF	TEMPORARY 24'' STOP BAR (PAINT)	646.66	-
						35	35	EA	LINE STRIPING TARGETS	646.76	-
						500	500	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	-
					400		400	SY	GEOTEXTILE FOR SILT FENCE	649.51	-
					60		60	LB	SEED	651.15	EST.
					10		10	LB	SEED-WINTER RYE	651.17	EST.
					500		500	LB	FERTILIZER	651.18	EST.
					2		2	TON	AGRICULTURAL LIMESTONE	651.20	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: WELLS
PROJECT NUMBER: VT RTE. 30

FILE NAME: /sqdc/98b160/db160frm.dgn
PROJECT LEADER: G. DUBRY
DESIGNED BY: A.JONES
QUANTITY SHEET I

PLOT DATE: 08-FEB-2006
DRAWN BY: A.JONES
CHECKED BY: B.DELLASANTA
SHEET 3 OF 32