STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET # 2

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

NON-GOV'T PARTICIPATING BRIDGE	NON-GOV'T PARTICIPATING ROADWAY	GOV'T PARTICIPATING BRIDGE	GOV'T PARTICIPATING ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
		24		24	m	HEAVY DUTY STEEL BEAM GUARD RAIL	621.21	0.4
			44	44	EA	MANUFACTURED TERMINAL SECTION (FLARED)	621.505	0
			7	7	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	0
			342	342	m	REMOVING AND RESET GUARDRAIL	621. 75	15.2
			290	250	EA	REPLACE GUARD RAIL POST ASSEMBLY	621. 76	EST.
			130	130	EA	REPLACE GUARD RAIL BEAM UNIT	621.77	EST.
			1926.6	1926.2	m	REMOVAL AND DISPOSAL OF GUARD RAIL	621.80	1.8
			990	990	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
			1,475	1,475	HR	FLAGGERS	630.15	EST.
			1	1	LS	FIELD OFFICE - ENGINEERS	631.10	--
			1	1	LS	TESTING EQUIPMENT - BITUMINOUS (MOD.)	631.17	--
			1	1	LU	FIELD OFFICE - TELEPHONE (N.A.B.1)	631.25	--
	520			520	HR	EMPLOYEE TRAINEESHIP	634.10	--
			1	1	LS	MOBILIZATION	635.10	--
			1	1	LS	TRAFFIC CONTROL	641.10	
			2	2	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	
			33,500	33,500	m	DURABLE 100mm WHITE LINE	646.40	121
			31,750	31,750	m	DURABLE 100mm YELLOW LINE	646.41	255
			260	260	m	DURABLE 200mm YELLOW LINE	646.43	3.8
			140	140	m	DURABLE 600mm STOP BAR	646.46	9.5
			124	124	EA	DURABLE LETTER OR SYMBOL	646.50	0
			34,250	34,250	m	TEMPORARY 100mm WHITE LINE	646.60	357
			32,300	32,300	m	TEMPORARY 100mm YELLOW LINE	646.61	291
			260	260	m	TEMPORARY 200mm YELLOW LINE	646.63	3.8
			275	275	m	TEMPORARY 600mm STOP BAR	646.66	14.0
			160	160	EA	TEMPORARY LETTERS OR SYMBOLS	646.70	2
			1,370	1,370	EA	LINE STRIPING TARGETS	646.76	9
			650	650	m^2	GEOTEXTILE UNDER STONE FILL	649.31	2.0
			21	21	kg	SEED	651.15	0
			170	170	kg	FERTILIZER	651.18	1.7
			2	2	+	AGRICULTURAL LIMESTONE	651.20	0.65

ADDENDUM # 1

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT: POWNAL-BENNINGTON

PROJECT NO.: NH 2118(1)S

DESIGN FILE NAME: /pave/98b168/pb168.dgn
IPARM FILE NAME: pb168qs02.1
SURVEYED BY: ACT, SJL, RAL
SQUAD LEADER: JAV

PLOT DATE: 17-JAN-2006 14
SURVEY DATE:
DRAWN BY: ACT
SHEET: 4 OF 65