STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #6

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	NEW AND SALVAGED SIGNS: EA	SIGN DIMENSIONS: WIDTH (mm)	SIGN DIMENSIONS: HEIGHT (mm)	NEW AND SALVAGED SIGNS: "A"	"B"	SALV. SIGN	SALV. T.I.S.	EXIST. POST: RETAIN	EXIST. POST: SALVAGE	NEW SIGN POSTS: NO. OF POSTS	FLANGED CHANNEL kg/m: 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m: 44 / 3.4	50 / 3.9	63 / 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m: 75 / 1.9	100 / 2.5	100 MOD. / 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m: 75 / 11.3	89 / 13.4	100 / 16.1	125 / 21.7	W-SHAPE STEEL FTG. SIZE: 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
TRAILER PARK DRIVE 20+071, RT.	STOP	1	750	750	0.56						1			4.1 X			X																R 1-1		E-143M
VT ROUTE 346 10+088, RT.	WILLIAMSTOWN MA 4 ⇨	1	1800	250	0.45				X																								D 1-1 NEW SIGN TO BE MOUNTED ON RETAINED POSTS WITH RETAINED SIGNS		E-123M
10+088, LT.	POWNAL	1	1800	250	0.45						2			4.3 X			X																D 1-1		E-123M
	NORTH POWNAL 3	1	1800	250	0.45																												D 1-1		E-123M
10+120, LT.	SPEED LIMIT 35 / THROUGH WAY ENDS HERE / THROUGH WAY BEGINS HERE	1	600	750	0.45						1			4.9 X			X																R 2-1, VR - 040 BACK TO BACK		E-142M
		1	600	600	0.36																												VR - 041		E-141M
		1	600	600	0.36																														
10+122, RT.	NORTH 7 / SOUTH 7	2	600	300	0.36						2			4.9 X 4.9			X															X	M 3-1, M 3-3		E-136AM
		2	600	600	0.72																												M 1-4		E-136AM
		2	525	375	0.40																												M 6-1		E-136AM
10+170, RT.	R / END	1	600	600	0.36						1			4.1 X			X																R 8-3A		E-143M
		1	600	300	0.18																												M 4-6		E-140M
10+173, LT.	R / BEGIN	1	600	600	0.36						1			4.3 X			X																R 8-3A		E-143M
		1	600	300	0.18																												M 4-11		E-140M
10+190, RT.	NORTH / VERMONT 346	1	600	300	0.18						1			4.0 X			X																M 3-1		E-136BM
		1	750	600	0.45																														E-136BM
		m²	m²	EA.	m²							m	m	m 41.4	m	m	m 41.4		EA	kg	kg	kg		kg	kg	kg	kg							
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC AND SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."														39.8																					
	TOTALS	m² 6.27	m²	EA.	m²							m 41.4			m 41.4					kg	EA.	kg					EA.	EA.	kg						

PROJECT: POWNAL-BENNINGTON
PROJECT NO.: NH 2118(1)S
DESIGN FILE NAME: /pave/98b168/pb168.dgn
IPARM FILE NAME: pb168ts06.i
SURVEYED BY: ACT, SJL, RAL
SQUAD LEADER: JAV
PLOT DATE: 17-JAN-2006 14:3
SURVEY DATE:
DRAWN BY: ACT
SHEET: 49 OF 65