STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #14

VAOT Metric

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	NEW AND SALVAGED SIGNS: EA	SIGN DIMENSIONS: WIDTH (mm)	SIGN DIMENSIONS: HEIGHT (mm)	NEW AND SALVAGED SIGNS: "A"	NEW AND SALVAGED SIGNS: "B"	NEW AND SALVAGED SIGNS: SALV. SIGN	NEW AND SALVAGED SIGNS: SALV. T.I.S.	EXIST. POST: RETAIN	EXIST. POST: SALVAGE	NEW SIGN POSTS: NO. OF POSTS	FLANGED CHANNEL kg/m: 1.7	FLANGED CHANNEL kg/m: 3.0	FLANGED CHANNEL kg/m: 4.5	SQUARE STEEL (mm) kg/m: 44 (3.4)	SQUARE STEEL (mm) kg/m: 50 (3.9)	SQUARE STEEL (mm) kg/m: 63 (5.0)	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m: 75 (1.9)	TUBULAR ALUMINUM Ø (mm) kg/m: 100 (2.5)	TUBULAR ALUMINUM Ø (mm) kg/m: 100 MOD. (2.5)	TUBULAR STEEL Ø (mm): FOUNDATION	TUBULAR STEEL Ø (mm) kg/m: 75 (11.3)	TUBULAR STEEL Ø (mm) kg/m: 89 (13.4)	TUBULAR STEEL Ø (mm) kg/m: 100 (16.1)	TUBULAR STEEL Ø (mm) kg/m: 125 (21.7)	W-SHAPE STEEL: FTG. SIZE 600 mm	W-SHAPE STEEL: FTG. SIZE 750 mm	W-SHAPE STEEL: WEIGHT	W-SHAPE STEEL: POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STD. SHEET NUMBER
TOWN OF BENNINGTON																																			
2+662, RT.		1	750	750	0.56						1			X			X																	W 1- 2L		E-151M
		1	450	450	0.20																													W 13- 1		E-155M
2+885, RT.		1	1200	600	0.72						2			X			X																	W 1- 6		E-152M
	0070 0202 0180	1	150	200	0.03																													VD - 700		E-138M
3+041, RT.	REDUCED SPEED AHEAD	1	600	750	0.45						1			X			X																	R 2- 5A		E-142M
3+098, LT.	DO NOT PASS	1	600	750	0.45						1			X			X																	R 4-1		E-141M
3+156, LT.	SPEED LIMIT 50	1	600	750	0.45						1			X			X																	R 2-1		E-142M
3+163, RT.	SPEED LIMIT 40	1	600	750	0.45						1			X			X																	R 2-1		E-142M
3+294, RT.	REDUCED SPEED AHEAD	1	600	750	0.45						1			X			X																	R 2- 5A		E-142M
3+338, RT.	HIDDEN DRIVE LEFT	1	750	750	0.56						1			X			X																	VW - 133		E-154M
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC AND SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."		m²	m²	EA.	m²							m 41.4	m	m	m 41.4	m	m	EA	kg 23.0	kg	kg		kg	kg	kg	kg									
	TOTALS	m² 4.32	m²	EA.	m²		m 41.4			m 41.4			kg 23.0	EA.		kg			EA.	EA.	kg													

PROJECT: POWNAL-BENNINGTON
PROJECT NO.: NH 2118(I)S

DESIGN FILE NAME: /pave/98bl68/pbl68.dgn
IPARM FILE NAME: pbl68tsl4.i
SURVEYED BY: ACT, SJL, RAL
SQUAD LEADER: JAV

PLOT DATE: 17-JAN-2006 14
SURVEY DATE:
DRAWN BY: ACT
SHEET: 57 OF 65