STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
ROCHESTER:																																			
11+498.1, RT	TO NORTH HOLLOW						1				1		X			X																	SALVAGED SIGNS TO BE MOUNTED ON NEW POST.	-	-
	QUARRY RD						1																											-	-
HANCOCK:																																			
0+603.0, LT	TUNNEL BROOK RD						1				1			X		X																	SALVAGED SIGNS TO BE MOUNTED ON NEW POST.		-
	STOP						1																											MOUNT MILEMARKER BACK TO BACK WITH STOP SIGN ON NEW POST		-
	1000 0108 0038						1																												-
1+381.0, RT	1000 0108 0086	1	150	200	0.03																													MOUNT NEW MILEMARKER BACK TO BACK WITH STOP SIGN ON EXISTING POST		E-138
												m	m 4.6	m 4.6	m	m 9.2	m		EA	kg	kg	kg		kg	kg	kg	kg							
TOTALS			m^2 0.03	m^2	EA 5	m^2						m 9.2			m 9.2					kg			EA	kg				EA	EA	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: ROCHESTER - GRANVILLE
PROJECT NO.: AC STP 2124(I)S

DESIGN FILE NAME: /pave/98bl80/pbl80.dgn
IPARM FILE NAME: pbl08t01.i
PLOT DATE: 21-DEC-2006 15:
SURVEYED BY: N/A
SURVEY DATE: N/A
SQUAD LEADER: T.P.K.
DRAWN BY: C.A.K.
SHEET: 32 OF 49