STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

| KILOMETER MARKER, STATION, OR SIGN NUMBER | SIGN LEGEND | SIGN DIMENSIONS EA | WIDTH (mm) | HEIGHT (mm) | NEW & SALVAGED SIGNS "A" | "B" | SALV SIGN | SALV TIS | EXIST POST RETAIN | SALVAGE | NEW SIGN POSTS NO. OF POSTS | FLANGED CHANNEL 1.7 kg/m | 3.0 kg/m | 4.5 kg/m | SQUARE STEEL (mm) 44 kg/m | 50 kg/m | 63 kg/m | ANCHOR | SLEEVE | TUBULAR ALUMINUM Ø (mm) 75 kg/m | 100 kg/m | 100 MOD kg/m | FOUND-ATION | TUBULAR STEEL Ø (mm) 75 kg/m | 89 kg/m | 100 kg/m | 125 kg/m | W-SHAPE STEEL FTG. SIZE 600 mm | 750 mm | WEIGHT | POST SIZE | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL DETAIL ON SHEET NUMBER | STD. SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| HANCOCK: | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1+945.0, LT | STOP 1000 0108 0121 | 1<br>1 | 750<br>150 | 750<br>200 | 0.56<br>0.03 | | | | | | 1 | | | X | | X | | | | | | | | | | | | | | | | | BACK-TO-BACK | | E-143<br>E-138 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 2+051.0, LT | 1000 0108 0128 | 1 | 150 | 200 | 0.03 | | | | | | | | | | | | | | | | | | | | | | | | | | | | MOUNT NEW MILEMARKER BACK TO BACK WITH STOP SIGN ON EXISTING POST | | E-138 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 3+825.0, RT | | 1 | 300 | 900 | 0.27 | | | | | | 1 | | | X | | X | | | | | | | | | | | | | | | | | | 48 | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 3+830.6, LT | | 1 | 300 | 900 | 0.27 | | | | | | 1 | | | X | | X | | | | | | | | | | | | | | | | | | 48 | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 3+833.0, RT | | 1 | 300 | 900 | 0.27 | | | | | | 1 | | | X | | X | | | | | | | | | | | | | | | | | | 48 | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 3+836.0, LT | | 1 | 300 | 900 | 0.27 | | | | | | 1 | | | X | | X | | | | | | | | | | | | | | | | | | 48 | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | m | m | m 23.0 | m | m 23.0 | m | | EA | kg | kg | kg | | kg | kg | kg | kg | | | | | | | | |
| **TOTALS** | | | | | m² 1.70 | m² | EA | m² | | | | m 23.0 | | | m 23.0 | | | | | kg | | | EA | kg | | | | EA | EA | kg | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

| | |
|---|---|
| PROJECT: ROCHESTER - - GRANVILLE | PROJECT NO.: AC STP 2124(1)S |
| DESIGN FILE NAME: /pave/98b180/pb180.dgn | |
| IPARM FILE NAME: pb180t02.I | PLOT DATE: 21-DEC-2006 15: |
| SURVEYED BY: N/A | SURVEY DATE: N/A |
| SQUAD LEADER: T.P.K. | DRAWN BY: C.A.K. |
| | SHEET: 33 OF 49 |