STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL FOUNDATION	Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
	SHEET SUBTOTALS																																			
	SHEET 32 SUBTOTALS				0.03		5						4.6	4.6		9.2																				
	SHEET 33 SUBTOTALS				1.70		--						--	23.0		23.0																				
	SHEET 34 SUBTOTALS				1.14		--						--	18.4		18.4																				
	ROUNDING				0.13		--						0.4	4.0		4.4																				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

		m	m	m	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg																		
			5	50		55																														
TOTALS	m^2 3.00	m^2	EA 5	m^2		m 55		m 55		kg	EA	kg																								

PROJECT: ROCHESTER - - GRANVILLE	PROJECT NO.: AC STP 2124(I)S
DESIGN FILE NAME: /pave/98bl80/pbl80.dgn	
IPARM FILE NAME: pbl80t04.I	PLOT DATE: 21-DEC-2006 15:3
SURVEYED BY: N/A	SURVEY DATE: N/A
SQUAD LEADER: T.P.K.	DRAWN BY: C.A.K.
	SHEET: 35 OF 49