

QUANTITY SHEET 3

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
					ROADWAY	TRAINING	FULL C.E.	EROSION CONTROL	BRIDGE	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					500					500		MGAL	DUST CONTROL WITH WATER	609.10				
					6					6		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15				
					20					20		CY	STONE FILL, TYPE I	613.10				
									2900	2900		CY	STONE FILL, TYPE IV	613.13				
					1420					1420		LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28				
					1					1		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10				
					270					270		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10				
					55					55		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 8 INCH	618.11				
					24					24		SF	DETECTABLE WARNING SURFACE	618.30				
					12					12		EACH	YIELDING MARKER POSTS	619.17				
					30					30		LF	REMOVING AND RESETTING FENCE	620.50				
					270					270		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.215				
					1					1		EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50				
					3					3		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
					460					460		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
					5600					5600		HR	FLAGGERS	630.15				
							1			1		LS	FIELD OFFICE, ENGINEERS	631.10				
							1			1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
							1			1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
							3000			3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
						1040				1040		HR	EMPLOYEE TRAINEESHIP	634.10				
					1					1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
					6					6		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
					3500					3500		LF	DURABLE 4 INCH WHITE LINE, RECESSED POLYUREA	646.406				
					3150					3150		LF	DURABLE 4 INCH YELLOW LINE, RECESSED POLYUREA	646.416				
					60					60		LF	DURABLE 24 INCH STOP BAR, RECESSED POLYUREA	646.486				
					23					23		EACH	DURABLE LETTER OR SYMBOL, POLYUREA	646.494				
					4900					4900		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11				
					85				1650	1735		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								100		100		SY	GEOTEXTILE FOR SILT FENCE	649.51				
								290		290		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
								320		320		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
								770		770		LB	SEED	651.15				
								4800		4800		LB	FERTILIZER	651.18				
								20		20		TON	AGRICULTURAL LIMESTONE	651.20				
								20		20		TON	HAY MULCH	651.25				
								1310		1310		CY	TOPSOIL	651.35				
									1300	1300		SY	GRUBBING MATERIAL	651.40				
								1		1		LS	EPSC PLAN	652.10				
								576		576		HR	MONITORING EPSC PLAN	652.20				

PROJECT NAME: EAST MONTPELIER
 PROJECT NUMBER: BRF 037-I(7)
 FILE NAME: 06_Quantities.dgn
 PROJECT LEADER: T. KNIGHT
 DESIGNED BY: K. RICHARDSON
 QUANTITY SHEET 05 3
 PLOT DATE: 2/17/2017
 DRAWN BY: C. GENDRON
 CHECKED BY: D. YOULEN
 SHEET 8 OF 158

